PROJECT	DESIGNATION
PB-14-0004	PB-14-0004
CONTRACT	BRIDGE FILE
	Hamilton Co. Br. 306

STRUCTURE	TYPE	SPAN AND SKEW	OVER	STATION
HAMILTON CO. BRIDGE	REINFORCED CONCRETE SLAB	27'-0" SPAN 25°00'00" SKEW	FRANK KEISER DRAIN	59+48.00

# HAMILTON COUNTY HIGHWAY DEPARTMENT

REPLACEMENT PLAN FOR
SMALL STRUCTURE NO. 23034 (BRIDGE NO. 306)
CYNTHEANNE ROAD OVER FRANK KEISER DRAIN
WAYNE TOWNSHIP
PB-14-0004



APPROVED BY:
HAMILTON COUNTY BOARD OF COMMISSIONERS

Date: May 22, 3017

Christine Altman

President

Vice President

Member

Auditor


Mark Heirbra dt


Steven C. Dillinger

Robin m Miles

Robin M. Mills

Thurman, P.E. Acting County Highway En







LATITUDE: 40°00'33"N	LONGITUDE: 85°52'5	3"W
BRIDGE LENGTH:	0.008	M
ROADWAY LENGTH:	0.229	M
TOTAL LENGTH:	0.237	M
MAX. GRADE:	2.95	%


# **GENERAL NOTES**


 Notify the Hamilton County Surveyor's Office at 317-776-8495 a minimum of 30 days prior to construction per Indiana Code. The placement of a benchmark by the Contractor will be required as a part of this project. See Section Corner Monument and Benchmark Placement Special Provision for additional information.


> INDIANA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS DATED 2016 TO BE USED WITH THESE PLANS



SOIL CONSULTANTS
EARTH EXPLORATION, INC.
7770 West New York St
Indianapolis, Indiana, 46214
(317) 273-1690







# UTILITIES

**ELECTRIC** Duke Energy 100 S. Mill Creek Road Noblesville, IN 46062 Contact: Brynn Streeter (317)-703-0681 Brynn.streeter@duke-energy.com

WATER

**COMMUNICATIONS** 240 N Meridian Street Indianapolis, IN 46204 Contact: Brian Cravens (317)-796-5793 BC85@attn.com

Comcast 5330 East 65th Street Indianapolis, IN 46220 Contact: Thomas Spencer (317)-752-9426 tspencer@telecomplacement.com

CEG Water
2150 Dr. Martin Luther King Jr. Street
Indianapolis, IN 46202
Contact: Chris Brumfield
(317)-695-0978
CBrumfield@citizensenergygroup.com



# **INDEX**

	INDEX
SHEET NO.	DESCRIPTION
	DIVISION A - CYNTHEANNE ROAD OVER FRANK KEISER DRAIN
1	TITLE SHEET
2	INDEX AND GENERAL NOTES
3	LOCATION CONTROL ROUTE SURVEY
4-5	TYPICAL CROSS SECTIONS
6	MAINTENANCE OF TRAFFIC
7-9	PLAN & PROFILE SHEETS
10-13	TEMPORARY EROSION CONTROL
14-15	PAVEMENT MARKING AND SIGNING
16	SOIL BORINGS
17-18	GENERAL PLAN
19	FOUNDATION LAYOUT
20-22	END BENT #1 & #2 CONSTRUCTION & DETAILS
23-24	SUPERSTRUCTURE DETAILS
25	SCREED DETAILS
26	R.C. BRIDGE APPROACH
27	BRIDGE SUMMARY OF QUANTITIES
28	ROAD SUMMARY
29	PAVEMENT QUANTITIES AND APPROACH TABLE
30	STRUCTURE DATA TABLE AND PIPE MATERIAL TABLE
31-39	CROSS SECTIONS
	DIVISION B - WETLAND MITIGATION
1 - 10	WETLAND MITIGATION PLANS

REVISIONS				
DATE	REVISED			
	DATE			

	RECOMMENDED FOR APPROVAL	B. K. A.	DESIGN ENGINEER	04/28/2017 R DATE	
IIIIIIIIIIIIIII	DESIGNED:	BSS	DRAWN:	DJG	
	CHECKED:	ВКА	CHECKED:	BSS	

LIANATI TONI COLINITY	HORIZONTAL SCALE	BRIDGE FILE		
HAMILTON COUNTY HIGHWAY DEPARTMENT	N/A	HAMILTON CO. BR. 306		
	VERTICAL SCALE	DESIGNATION		
	N/A	PB-14-0004		
	SURVEY BOOK	SHEETS		
NDEX AND GENERAL NOTES		2	of	39
NOLA AND GLINERAL NOTES	CONTRACT	PROJECT		
		DD 14 0004		

#### SURVEYOR'S REPORT

ROUTE SURVEY for Bridge 306 and Small Structure #23034, on Cyntheanne Road over Keiser Drain between 146th Street and 156th Street. OWNER/CLIENT: Hamilton County, Indiana.

LOCATED in Sections 17 and 18, Township 18 North, Range 6 East, Wayne Township, Hamilton County, Indiana.

The purpose of this survey is to collect data for the design of a bridge/small structure project, and to provide a basis of describing any right-of-way needed for the project. It is not a property retracement survey.

Field measurements for this survey were made in accordance with specifications for Urban Surveys as outlined in the Indiana Administrative Code (865 IAC 1-12 "Rule 12"), with a "Relative Positional Accuracy" of plus or minus 0.07 feet plus 50 parts per million. The "Relative Positional Accuracy" relates to the accuracy limitations of the measurements made this survey (including the cumulative effects of measurement errors).

Coordinates and bearings used this survey are on the NAD83 Indiana East Zone State Plane Coordinate Grid, based on GPS observations using the Trimble VRS-Now network at Random Control Point #1400. This coordinate system was chosen for consistency with the Hamilton County Surveyor's published coordinates on section corners in the area.

All horizontal coordinate, distance, and stationing values shown are measured on the State Plane Grid. The grid-to-ground combined factor at the project location is 0.999957491, yielding a difference of about 0.22' per mile (43 parts-per-million) between ground-measured distances and coordinate inverses.

For many practical applications within the project area, the grid-ground factor can be ignored and the coordinates shown can be treated as local ground coordinates. However, for any applications requiring higher accuracies, any distance values shown, or generated from coordinates or stationing shown on this survey, should be scaled to ground by dividing by the Project Average Combined Factor of 0.999957491, before applying to measurements laid out on the ground. Likewise, any ground-measured distances should be scaled to grid by multiplying by 0.999957491 before using to generate coordinates or stationing in this project.


Line "A" is an original alignment, defined by the monuments set or found this survey, and therefore has no re-establishment uncertainty. Line "A" was established to follow the apparent section line as evidenced by the monuments shown.

#### Section Corners:

Points 6400, 6401, and 6402 all represent Harrison Monuments found in place, consistent with Hamilton County Surveyor Corner Records. Their positions as measured this survey agreed with the County Surveyor's published coordinates, well within the relative positional accuracy of this survey; the published coordinates were therefore held as published.

#### Existing Right-of-way:

No reference was found in adjoining deeds regarding the existing right-of-way of Cyntheanne Road. The Hamilton County Highway Department was contacted but was not able to provide documentary records of the existing right-of-way.



LEGEND

Description

MONUMENTED BASELINE CONTROL POINTS

PROPERTY / SECTION CORNER EVIDENCE

RANDOM CONTROL POINT

COORDINATE LISTING: RANDOM CONTROL POINTS

Northing

1733803.046

1733358.208

1733891.343

1403 1734499.467

Easting


267878.573

268002.028

268010.920

267942.863


SOCIAL SECURITY NUMBER REDACTION STATEMENT I affirm, under the penalties for perjury, that I have taken reasonable care to redact each social security number in this document, unless





Prepared By

SURVEY STARTED	
June 2, 2015	THIS SURV
SURVEY COMPLETED	ACCORDING SURVEYS,
June 4, 2015	DESCRIPTION PARCELS
ROUTE PLAT SHEETS	RECON
1 of 1	
SURVEYOR'S PROJECT NO.	17 er
214-0030-1BL	REGIS
·	



Prepared for the	HORIZONTAL SCALE
COMMISSIONERS OF	1" = 100'
	COUNTY
HAMILTON COUNTY, INDIANA	HAMILTON
LOCATION CONTROL ROUTE SURVEY	SURVEY BOOK
Bridge #306 and Small Structure #23034	
on Cyntheanne Road over Keiser Drain	CONTRACT

between 146th Street and 156th Street

Mag Nail Up 2'

in SW Side of

PwP #062-211

See Ref. on File

in Co. Surveyor's

office for E. 1/4

Cor. Sec. 18-18-6

Mag Nail Up 2'

PwP #62-215

Mag Nail in N

BRIDGE FILE

HAMILTON CO. BR. 306

DESIGNATION

PB-14-0004


PLAN SHEETS

PROJECT

PB-14-0004

of 39

Util. Pole



BKA

BSS


PB-14-0004

CHECKED:

R/W Varies 9'-3" to 60'-0"

R/W Varies 10'-7" to 45'-0"


C.Z. Clear Zone



See Guardrail Table for Locations
Varies
Varies
Varies
Varies
Varies

Limits of Subgrade Treatment

Typical Guardrail Section Line "A"
Sta. 58+48.29 to Sta. 59+05.44 Lt.



Every 100 Feet, Extend Aggregate to Slope for a Width of 1 Foot.

12'-0" 4'-0" 1'-5" 2'-0" Varies Varies

Thru Lane Shldr. See Guardrail Table for Location

2%
2%
2%
20:1

4:1

Limits of Subgrade Treatment

Typical Guardrail Section Line "A"

Sta. 57+88.21 to Sta. 59+05.44 Rt.

EARTHWORK SUMMARY TAB	LE	
COMMON EXCAVATION		
Line "A"	7,180	CYD
Undercut for STR NO. 12	35	CYD
Undercut for Poor Soils	520	CYD
Common Excavation for Bridge	271	CYD
TOTAL COMMON EXCAVATION	8,010	CYD
Less Unuseable Excavation	1,630	CYD
TOTAL USEABLE EXCAVATION	6,380	CYD
FILL		
Line "A"	18,205	CYD
Subtotal, Available Fill	18,205	CYD
Swell (15%)	2,735	CYD
TOTAL FILL VOLUME REQ'D	20,940	CYD
Less Useable Excavation	6,380	CYD
TOTAL BORROW REQ'D	14,560	CYD
EXCAVATION, FOUNDATION, UNCLASSIFIED	265	CYD
BENCHING*	255	CYD
*Benching is Not Paid for Directly		

Note: All Disturbed Areas Shall Have Erosion Control Blanket and See Mixture, R; Unless Otherwise Shown.

**LEGEND** 

C.Z. Clear Zone


- K 165#/SYD. QC/QA HMA, 2, 64 Surface, 9.5mm on 275#/SYD. QC/QA HMA, 2, 64, Intermediate, 19.0mm on 330#/SYD. QC/QA HMA, 2, 64, Base, 25.0mm on 6 in. Compacted Aggregate No. 53, Base on Subgrade Treatment, Type I
  - K1 165#/SYD. QC/QA HMA, 2, 64 Surface, 9.5mm on 275#/SYD. QC/QA HMA, 2, 64, Intermediate, 19.0mm on 330#/SYD. QC/QA HMA, 2, 64, Base, 25.0mm on 6 in. Compacted Aggregate No. 53, Base on Subgrade Treatment, Type IC
- O 13 in. Compacted Aggregate, No. 53, on Subgrade Treatment, Type I
- O1) 13 in. Compacted Aggregate, No. 53, on Subgrade Treatment, Type IC
- 26 Erosion Control Blanket & Seed Mixture, R



RECOMMENDE FOR APPROVA	B. K. B.	DESIGN ENGINEER	04/28/2017 DATE	
DESIGNED:	BSS	DRAWN:	DJG	
CHECKED:	ВКА	CHECKED:	BSS	

LIANATI TONI COLINITY	HORIZONTAL SCALE	BRIDGE FILE			
HAMILTON COUNTY	3/8"=1'-0"	HAMILTON CO. BR. 306			
HIGHWAY DEPARTMENT	VERTICAL SCALE	DESIGNATION		ION	
	N/A	PB-14-0004			
	SURVEY BOOK	SHEETS			
YPICAL CROSS SECTIONS		5	of	39	
TPICAL CROSS SECTIONS	CONTRACT	PROJECT PB-14-0004			

Date: Jun 06, 2017, 4:38pm User Name: barterber File: M:∟2014|214-0030|Road|CAD|MiscDWG|Typi



<u>Detour</u>

- 1. Cyntheanne Road Shall Be Closed To Thru Traffic From 146th Street To 156th Street. Detour Cyntheanne Road Traffic West On 146th Street To Prairie Baptist Rd., North On Prairie Baptist Rd. To 156th Street, & East On 156th To Cyntheanne Road.
- 2. Detour Shall Remain In Place Throughout Construction.
- 3. Contractor Shall Maintain Temporary Access To All Properties During Construction.

# Legend

- A Std. Barricade, Type III-A (Feet Req'd.)
- B Std. Barricade, Type III-B (Feet Req'd.)
- C Construction Sign A, XG20-3 (Road Closed Ahead) w/ W20-7 (500 Feet)
- (E) Construction Sign A, XG20-3 (Road Closed Ahead)
- (F) Construction Sign B, XG20-2 (End Construction)
- G Construction Sign A, XW20-2 (Detour Ahead)
- (H) Construction Sign A, R11-2 (Road Closed)
- (K) Construction Sign, C, XW2-6-A (Worksite Penalty)
- L Road Closure Sign Assembly; R11-3 (Road Closed X.X Miles Ahead Local Traffic Only) w/ M4-10 (L or R) (Detour Arrow)
- T Detour Route Marker
- TT Construction Sign
- ⊗ Construction Warning Light, A \*\* Construction Warning Light, B
- □ Std. Barricade
- Work Area Detour Route

DETOUR Cyntheanne Ro

DRM-1 XM4-8

Sign A M6-1(S)

Cyntheanne Ro

DRM-2 XM4-8

DETOUR

Sign A M6-1(S)

DETOUR



DETOUR

DRM-4 XM4-8 Sign A M5-1(L)(S)

DRM-5 XM4-8 Sign A M5-1(R)(S)

Cyntheanne


Cyntheanne Ro DRM-6 XM4-6(S) XM4-8 Sign A


MAINTENANCE OF TRAFFIC QUANTITIES							
Construction Sign, A	Construction Sign, B	Construction Sign, C	Road Closure Sign Assembly	Detour Route Marker Assembly	Barricade, III-A	Barricade, III-B	
Each	Each	Each	Each	Each	LFT	LFT	
8	2 2 2 12 48						


MAINTENANCE OF TRAFFIC QUANTITIES							
Construction Sign, A	Construction Sign, B	Construction Sign, B Construction Sign, C Road Closure Sign Assembly Detour Route Marker Assembly Barricade, III-A Barricade, III-B					
Each	Each	Each	Each	Each	LFT	LFT	
8	2						


RECOMMENDED B. K B. C DESIGN ENGINEER 04/28/2017 DESIGN ENGINEER DATE	
DESIGNED: DJG	
CHECKED: BKA CHECKED: BSS	


LIANATI TONI COLINITY	HORIZONTAL SCALE	BRIDGE FILE
HAMILTON COUNTY	1"=2000'	HAMILTON CO. BR. 306
HIGHWAY DEPARTMENT	VERTICAL SCALE	DESIGNATION
	N/A	PB-14-0004
	SURVEY BOOK	SHEETS
MAINTENANCE OF TRAFFIC		6 of 39
MAINTLINANCE OF TRAFFIC	CONTRACT	PROJECT
		PB-14-0004











					7	ΓEMPORA	RY EROS	SION CONT	ΓROL TA	BLE			
LOCATIO	N R	MEDIAN	RIGHT	PERIMETER PROTECTION	TEMPORARY SEDIMENT TRAP	SEDIMENT BASIN	SLOPE DRAIN	TEMPORARY CHECK DAM, REVETMENT RIPRAP	STRAW BALES DITCH CHECK	RIPRAP DITCH CHECK	DITCH INLET PROTECTION	FISH POOL	REMARKS
		_		LFT	TON	EACH	LFT	TON	LFT	CYS	EACH	EACH	
52+20.00			X					14					
53+40.00			Х					14					
53+80.00			Х					14					
55+00.00			Х					14					
62+40.00			Х					14					
58+26.00	X							32					
59+62.00	X							14					
60+67.00	X							14					
61+14.00	X							14					
62+34.00	X							14					
63+55.00	X							14					
63+95.00	X							14					
64+35.00	X							14					
TOTAL								200					

	•					70.	*-	_ ~					1
	TEMPORARY EROSION CONTROL TABLE												
LOCATIO	LOCATION RS ST F SS T TS T												
STATION		MEDIAN	RIGHT	PERIMETER PROTECTION	TEMPORARY SEDIMENT TRAP	SEDIMENT BASIN	SLOPE DRAIN	TEMPORARY CHECK DAM, REVETMENT RIPRAP	STRAW BALES DITCH CHECK	RIPRAP DITCH CHECK	DITCH INLET PROTECTION	FISH POOL	REMARKS
				LFT	TON	EACH	LFT	TON	LFT	CYS	EACH	EACH	
64+75.00	X							14					
64+75.00			Х					14					
55+98.00			X		14								
56+19.00			X		14								
56+26.00	X				32								
59+25.00			Х		14								
60+00.00			X		14								
50+79 to 63+29	Х			1210									
54+25 to 64+75			Х	991									
63+50.00	X										1		
	$\perp \perp$												
TOTAL				2201	88			28			1		


Note: All Disturbed Areas Shall Have Erosion Control Blanket and See Mixture, R; Unless Otherwise Shown.




RECOMMENDED FOR APPROVAL	B: KE		DESIGN ENGINEER	04/2	8/2017 DATE	
DESIGNED:	BSS	_	DRAWN:	DJG		
CHECKED:	ВКА		CHECKED:	BSS		

HAMILTON COUNTY HIGHWAY DEPARTMENT	
TEMPORARY EROSION CONTROL STA. 61+00.00 TO STA. 67+00.00	

HORIZONTAL SCALE	BRI	DGE F	TLE	
1"=20'	HAMILTON CO. BR. 306			
VERTICAL SCALE	DESIGNATION			
N/A	PB-14-0004			
SURVEY BOOK	SHEETS			
	11	of	39	
CONTRACT	PROJECT			
	PB-14-0004			
	1"=20' VERTICAL SCALE N/A SURVEY BOOK	1"=20' HAMILTO VERTICAL SCALE DESI N/A PB- SURVEY BOOK S 11 CONTRACT PF	1"=20' HAMILTON CO VERTICAL SCALE DESIGNAT N/A PB-14-00 SURVEY BOOK SHEET 11 of CONTRACT PROJECT	





# PUMP-AROUND PRACTICE P FOR CULVERT CONSTRUCTION NOT TO SCALE


# PUMP-AROUND


- 1.) Dewatering of the project area shall be performed using a mechanical pump. A dewatering (filter) bag shall be securely connected to the end of the discharge hose. The suction hose shall be floated as long as possible to prevent the pump from pulling sediment from the bottom of the pooled area.
- 2.) The dewatering bag may be of the single-use or reusable variety and shall be constructed of non-woven, polypropylene geotextile material. Each type and size of dewatering bag can handle varying rates of flow. The bag shall have for following minimum specifications:


Apparent Opening Size

Permittivity Grab Tensile Wei 1.4 sec 205 lbs 8 oz


- 1.4 sec 205 lbs 8 oz/syd 80 US Sieve3.) The dewatering bag shall be placed on a flat surface. Placing the dewatering bag on top of an aggregate base or straw bales will help to increase to flow through the fabric by
- providing a larger surface area of discharge.4.) Water shall not be pumped from the project area at a rate faster than the manufacturer's maximum recommended flow rate of the dewatering bag.
- 5.) Dewatering bags shall be placed in a location in which runoff will pass through additional sediment control measures prior to entering the storm sewer.
- 6.) Following completion of dewatering, the sediment accumulated within the dewatering bag shall be removed from the bag and placed in an uplan area.







# CONCRETE WASHOUT - ABOVE GRADE SYSTEM



#### CONCRETE WASHOUT - BELOW GRADE SYSTEM

#### Location:

- \* Locate concrete washout systems at least 50 feet from any creek, wetlands, ditches, karst features, or storm
- drains/man made conveyance systems.

  \* To the extent practical, locate concrete washout systems in relatively flat areas that have established vegetative cover and do not receive runoff from adjacent land areas.
- \* Locate in areas that provide easy access for the concrete trucks and other construction equipment.

  \* Locate away from other construction traffic to reduce the potential for damage to system.

#### Materials:

- \* Minimum of ten millimeter polyethylene sheeting that is free of holes, tears, and other defects. The sheeting selected should be of appropriate size to fit the washout system without seams or overlap of the lining.
- \* Signage

  \* Orange safety fencing or equivalent.
- \* Straw bales, sandbags (bags should be ultraviolet-stabilized geotextile fabric), soil material, or other
- appropriate materials that can be used to construct a containment system (above grade system)
- \* Metal pins or staples at a minimum of six inches in length, sandbags, or alternate fasteners to secure polyethylene lining to the containment system.
- \* Non-collapsing and non-water holding cover for use during rain events. (optional)

# Installation:

- \* Utilize and follow the design in the storm water pollution prevention plan to install the system.
- \* Dependent on the type of system, either excavate the pit or install the containment system.
- \* A base shall be constructed an prepared that is free of rocks and other debris that may cause tears or punctures in the polyethylene lining.
  \* Install the polyethylene lining. For excavated systems, the lining should be extended over the entire excavation. The lining
- for bermed system should be installed over the pooling area with enough material to extend the lining over the berm or containment system. The lining should be secured with pins, staples,or other fasteners.
- \* Place flags, safety fencing, or equivalent to provide a barrier to construction equipment and other traffic.
- \* Place non-collapsing, non-water holding cover over the washout facility prior to predicted rainfall event to prevent accumulation of water and possible overflow of the system (optional).
- \* Install signage that identifies concrete washout areas.
- \* Post signs directing contractors and suppliers to designated locations.
- \* Where necessary, provide stable ingress and egress or alternative approach pad for concrete washout systems.



## CONCRETE WASHOUT DETAIL

\* NOT PAID FOR SEPARATELY

HAMILTON COUNTY

ARTE ON STERE STATE NO.
19800103
STATE OF ANDIANA STATE

RECOMMENDED FOR APPROVAL	B. K Sale	DESIGN ENGINEER	04/28/2017 DATE	
DESIGNED:	BSS	DRAWN:	DJG	
CHECKED:	ВКА	CHECKED:	BSS	
			<u> </u>	

HIGHWAY DEPARTMENT	
TEMPORARY EROSION CONTROL	
DETAILS	

HORIZONTAL SCALE	BRIDGE FILE							
1"=20'	HAMILTON CO. BR. 306							
VERTICAL SCALE	DESIGNATION							
N/A	PB-	-14-000	04					
SURVEY BOOK	SHEETS							
	12	of	39					
CONTRACT	PROJECT							
	PB-	-14-000	)4					

N:\L2014\214-0030\Road\CAD\Erosion\Temp Erosion Control.dwg

#### Construction Plan Elements (Section A)

- A-1 Index showing locations of required Plan Elements.
  Sheet 13 (This Sheet)
- A-2 11x17 inch plat showing building lot numbers/boundaries and road layout/names. Sheet 3 contains location information.
- A-3 Narrative describing the nature and purpose of the project.

The proposed project will consist of construction of a new 27-foot span bridge, while reconstructing and raising the profile of Cyntheanne Road.

- A-4 Vicinity map showing project location.

  Sheet 1 (Title Sheet)
- A-5 Legal Description of the Project Site

Specifically, the project site is located in: Indiana, Hamilton County, Township: 18N, Range: 6E, Section: 17 & 18, Civil Township: Wayne, Quarter: Multiple. The Latitude and Longitude for the center of the project is as follows: Latitude: 40°00'33" North, Longitude: 85°52'52" West

A-6 Location of all lots and proposed site improvements.

The bridge to be constructed and the anticipated work limits are shown on Sheets 7-9.

A-7 Hydrologic unit code (14 digit)

05120201110030 (Mud Creek - Headwaters)

A-8 Notation of any State or Federal water quality permits.

IDEM 401 Water Quality Certification USACE Section 404 permit

Rule 5 permit IDNR CIF

 $\boxed{A-9}$  Specific points where stormwater discharge will leave the site.

Stormwater will sheet flow from the site - it will migrate its way into an un-named tributary to

Mud Creek - see Plan and Profile view on Sheets 7-9.

- Location and name of all wetlands, lakes and water courses on and adjacent to the site.

  No wetlands or lakes are located within the project limits. An un-named tributary to Mud Creek is located nearby but not within the project limits.
- $\overline{A-11}$  Identification of all receiving waters.

Entirety of the project runoff will be deposited into un-named tributary to Mud Creek.

|A-12| Identification of potential discharges to ground water.

There are no known areas within the project site where stormwater will be discharged to groundwater.

A-13 100 year floodplains, floodways, and floodway fringes.

Most of the project is within a 100-year floodplain. Enclosed map shows the impacted location.

- A-14 Pre-construction and post construction estimate of Peak Discharge (10 year storm event)

  Due to the nature of the project, bridge construction and construction of existing road; there will be no significant change in the pre-construction to post-construction peak discharge.
- ||A-15|| Adjacent landuse

Adjacent land is dominated by agricultural farm land and residential properties.

 $\sqrt{16}$  Locations and approximate boundaries of all disturbed areas.

Sheets 7-9 shows the anticipated work areas. Disturbance is anticipated to remain within the designated construction limits.

 $\boxed{A-17}$  Identification of existing vegetative cover.

Vegetation within right of way consists of grasses, shrubs and trees.

 $\overline{A-18}$  Soils map including soil descriptions and limitations.

Soil Map can be found in the USGS Soil Survey of Hamilton County, In. The construction site is mostly composed of Pn with a small amounts of MoC3 and HeF on each end of the project limits.

<u>Pn - Patton silty clay loam:</u> Slopes are 0 to 2 percent. This component is on depressions on till plains. The parent material consists of loamy glaciolacustrine deposits over loamy outwash. Depth to a root restrictive layer is greater than 60 inches. The natural drainage class is poorly drained. Water movement in the most restrictive layer is moderately high. Available water to a depth of 60 inches (or restricted depth) is high. Shrink-swell potential is moderate. This soil is not flooded. It is frequently ponded.

MoC3 - Miami clay loam: Slopes are 6 to 12 percent. This component is on till plains, till plains. The parent material consists of loamy till. Depth to a root restrictive layer, densic material, is 24 to 40 inches. The natural drainage class is moderately well drained. Water movement in the most restrictive layer is low. Available water to a depth of 60 inches is low. Shrink-swell potential is low. This soil is not flooded. It is not ponded.

<u>HeF - Henepin loam:</u> Slopes are 18 to 50 percent. This component is on till plains. The parent material consists of loamy till. Depth to a root restrictive layer is greater than 60 inches. The natural drainage class is well drained. Water movement in the most restrictive layer is moderately low. Available water to a depth of 60 inches is low. Shrink-swell potential is low. This soil is not flooded. It is not ponded.

- $\boxed{A-19}$  Locations, size and dimensions of proposed stormwater systems.
- See Sheets 7-9 for location, size and dimensions of stormwater improvements.
- A-20 Plans for any off-site construction activities associated with this project. No offsite construction activities are proposed in association with this project.
- A-21 Locations of proposed soil stockpiles and/or borrow/disposal areas.

No off site disposal is anticipated for this project. If contractor decides that off site disposal is required an amended/additional Rule 5 plan shall be submitted in accordance with 327-IAC-15-5 for those areas not included in the Design Consultant's submittal or as necessary for changes initiated by the Contractor as per INDOT Standard Specification 108.04. The Contractor shall be responsible for all required disposal sites and obtaining all required permits associated with the disposal site activities in accordance with INDOT Standard Specification 203.08. Silt fence or other perimeter protection shall fully encompass the storage piles. Temporarily seed stockpiles which will be undisturbed for more than 7-days. Stockpiles shall not interfere with natural drainage, The use of stockpiles is anticipated to be minimal due the minimal space available on the site, however, if utilized, several small stockpiles, are usually more efficient and easier to contain than one large pile.

#### Stormwater Pollution Prevention Plan - Construction Component (Section B)

 $\boxed{B-1}$  Description of potential pollutant sources associated with the construction activities:

Potential pollutant sources associated with the construction activity include those normally associated with construction equipment, such as: concrete washout water, oils, fuels, hydraulic fluids, transmission fluids, brake fluid, antifreeze, greases, brake dust, etc. All heavy equipment shall be parked on site at a specific location, when not in use; leakage from the equipment will be captured by the surrounding terrain, and will not be provided a direct path to the surrounding waterways or storm sewer system. Construction litter and trash is also a potential pollutant. Additionally, sediment generated from the construction activity and equipment is a potential pollutant.

#### B-2 Initial Setup:

Upon completion of the initial site inspection, and before any vegetation is removed from the site, this erosion and sediment control plan shall be implemented. The plan must be dynamic and ever changing as the project develops. Proper sequencing of work may reduce the amount of bare soil and therefore reduce the need for extensive erosion and sediment control measures. Continual maintenance and updating of the plan by the construction contractor is of utmost importance. Below is a general sequencing of events for this erosion and sediment control plan. While the Contractor shall dictate the actual sequencing of construction, erosion and sediment control measures shall be implemented as described below during each phase of construction.

- 1. Flag or denote all construction limits.
- 2. Establish areas for storage of potential pollutants (e.g. fuel storage, oils, hydraulic fluids, etc.)
- 3. A pre-construction meeting with the owner, contractor, appointed "trained individual" and Hamilton County SWCD is required.
- 4. Notify the IDEM and Hamilton County SWCD at least 48-hours prior to commencement of work.
- Identify and protect all existing vegetation designated to be undisturbed.
- 6. Install erosion and sediment control perimeter protection (see temporary erosion control plans/tables). Construction of road side ditches, diversion berms, and installation of silt fence prior to earth moving will greatly reduce the chance of sediment discharge; protecting adjacent property and reducing the chance of sediment discharge into jurisdictional waterways. Proposed locations for these measures are shown on the plans, but may need to be modified and/or replaced based on the phasing and locations of active construction.
- 7. Install concrete washouts where needed to ensure that no concrete washout water enters the stormwater system, comes in contact with the ground, or leaves the project limits. The concrete washouts shall be in accordance with the detail shown on the plans.

#### $\boxed{B-3}$ Construction Entrance:

The Contractor shall provide a stable construction entrance at all points where construction traffic will enter onto an existing road. The number and locations of the construction entrances will be dependent upon construction phasing and the amount of site disturbance. Contractor shall amend the plan in accordance with INDOT Standard Specification 108.04 to show the actual entrance locations at various stages of construction. At a minimum, construction entrances shall conform to INDOT Standard Drawing E 205-TECP-01.

 $\boxed{B-4}$  Sediment control measures for sheet flow areas:

<u>Silt Fence (SF):</u> Shall be installed as needed to protect adjacent properties from receiving sediment-laden runoff. Proposed locations for this measure is shown on the plans, but may need to be modified and/or replaced based on the phasing and locations of active construction. SF shall be installed per INDOT Standard Drawing E 205-TECP-02

<u>Vegetative Filter Strip (VFS)</u>: A vegetative filter strip is an area where the ground cover is to be left undisturbed to filter runoff from the disturbed drainage area. All existing vegetation located outside of the construction limits, shall not be disturbed, to act as vegetative filter strips. In some cases, no silt fence or filter socks may be needed if a minimum 20-foot vegetative filter is left between disturbed areas and the edge of the easement or a concentrated flow area.

#### B-5 Sediment control measures for concentrated flow areas:

<u>Temporary Sediment Trap (ST)</u>: Sediment traps shall be constructed in the locations shown on the plans to collect runoff and allow for sediment to drop out prior to discharge. STs shall be constructed in accordance with INDOT Standard Drawing E 205-TECD-03.

Temporary Check Dams (CD): Rip Rap Check dams are used to reduce erosion in a drainage channel by slowing the velocity of the flow. Check dams shall be installed as soon as possible upon grading of constructed channels. Check dams shall also be installed in existing channels that will be receiving flow until the new channels are constructed. Once ditches are to grade, permanent erosion control measures (seeding, mulching, and/or erosion control blankets) shall be placed as soon as possible after ditch grading is completed. During construction, if ditch flow patterns change, erosion control measure locations may need to be adjusted so that no areas are left unprotected. Check dams shall be installed "toe-to-crest" such that the spillway of the downstream check dam is at the same elevation of the toe of the upstream dam in accordance with INDOT Standard Drawing E 205-TECD-01.

<u>Erosion Control Blanket (ECB)</u>: Erosion control blankets shall be installed following grading and seeding of the specified roadside ditches to prevent erosion and assist with vegetation establishment. In areas of the roadside ditches where seeding and mulching has resulted in permanent vegetation reaching 100% coverage/70% density, no erosion control blankets will be needed.

[B-6] Storm sewer inlet protection measure locations and specifications:

<u>Inlet Protection (IP)</u>: Temporary drop inlet protection will be placed on the proposed inlet immediately after installation and be properly protected in accordance with INDOT standard drawings E-205-TECI-04 & 05. Other methods may be employed with prior approval of the Engineer and the MSD.

B-7 Runoff control measures:

<u>Concrete Washout (CW):</u> Concrete washout areas shall be installed and utilized as containment for washing equipment of uncured concrete and associated liquids. They shall be constructed according to details shown on the plans and the Indiana Storm Water Quality Manual. All concrete washout water shall be discharged to a concrete washout area. CW's will be placed a minimum of 50 feet from any body of water and located away from inlets and stormwater conveyances. They shall be placed on stable material and in such a manner that all washout water is captured and contained in the CW. Detail shown on Sheet 12.

<u>Dewatering (D):</u> All dewatering to remove standing water from disturbed areas of the project shall be performed through a properly sized filter bag, which will be placed behind an appropriately sized secondary containment measure in accordance with the detail shown on Sheet 12.

- B-8 Stormwater outlet protection specifications:
- Not Applicable
- B-9 Grade stabilization structure locations and specifications:

Not Applicable

A-22 Existing site topography.

See Plan and Profile Sheets 7-9 and Cross-Sections 31-39. A-23 Proposed final topography.

See Plan and Profile Sheets 7-9 and Cross-Sections 31-39.

B-10 Locations, dimensions, specifications and constr. details of each stormwater quality measure:

The location and dimensions of all stormwater quality measures can be found on Sheets 10-13. Additionally, construction details can be found in the Indiana Storm Water Quality Manual and INDOT Standard Drawings.

surface stabilization methods appropriate for each season:

Stormwater Pollution Prevention Plan - Construction Component (Section B)(Cont'd)

B-11 Temporary surface stabilization methods appropriate for each season:

Temporary surface stabilization shall be accomplished by the use of a temporary seed mixture along with temporary mulching. The temporary seed mixture shall be used to establish a temporary cover for disturbed soils during the construction operations. Temporary seeding shall be placed on disturbed areas that are expected to be undisturbed for more than 7 days or as directed by the Engineer. Placement of the temporary surface stabilization shall be per INDOT Standard Specifications, Section 205-R-636.

 $\boxed{B-12}$  Permanent surface stabilization specifications:

Where pavement is not proposed, permanent surface stabilization shall be achieved by the use of a permanent seed mixture, along with mulching material/erosion control blankets and fertilizer or sod. Placement of the permanent surface stabilization shall occur upon final grading of an area and shall be per INDOT Standard Specifications, Section 621-R-637, unless otherwise specified.

B-13 Material handling and spill prevention plan:

Any onsite storage of hazardous materials/potential pollutants, such as diesel fuel, shall be stored onsite surrounded by an earthen dike or other secondary containment system having a storage volume equal to 150% of tank capacity, to contain potential pollutants. Any additional means of containing releases should be accessible to a petroleum storage area; this would include various absorbent materials. In the event of a release, a licensed environmental consulting company, should be contacted for spill cleanup assistance. Furthermore, all equipment, when not in use, shall be parked onsite in an area that, should potential pollutants leak, will be contained within the immediate area and will not be inadvertently conveyed to drainage swales and away from the project. Any leakage of pollutants from storage vessels or equipment shall be cleaned up and disposed of offsite in a legal manner. In the event of a release, a licensed environmental consulting company shall be contacted for spill cleanup assistance. The spill shall be reported to both IDEM's 24-hour emergency response line at (888) 233-7745 and the MSD Bureau of Water Quality (765)747-4896.

B-14 Monitoring and maintenance guidelines for each proposed pollution prevention measure:

Temporary erosion and sediment control measures shall be self-inspected by Contractor personnel or their representative, knowledgeable in erosion and sediment control, once every seven days and within 24 hours of a 1/2 inch measurable storm event.

Inspections shall be documented and records shall be maintained by the Contractor and be made available for review upon request. Records shall include, at a minimum, date, inspector's name, maintenance and corrections needed based on the inspection, and status of previously identified deficiencies. INDOT Form 108-c-192d: Storm Water, Erosion, and Sediment Control Inspection Report is available on INDOT's website for use. The temporary protection measures shall be returned to good working condition within 48 hours after inspection or as directed. Inspections shall continue until the entire contract is complete and has been permanently stabilized and the Notice of Termination has been filed with the reviewing authority.

The following shall apply to maintaining the specific erosion and sediment control facilities:

- The Erosion and Sediment Control Measures shall be installed and maintained in accordance with the details shown in the drawings, INDOT Standard Specifications Section 205-R-637, INDOT Standard Drawings, and IDEM Storm Water Quality Manual.
- The Contractor or their representative, knowledgeable in erosion and sediment control, shall routinely inspect the overall performance of erosion and sediment control facilities and areas downstream of the project site. If eroded material/silt is apparent downstream from the facilities, some failure has occurred, and the inspector shall notify the Contractor and Engineer. The Contractor shall remove the accumulated sediment downstream and add additional erosion control measures to address the issues as necessary. The contractor shall implement all recommended solutions to the problem areas as recommended by the Engineer, IDEM, SWCD or Hamilton County SWCD inspector within 48 hours or as directed by the Engineer.

Following completion of construction and final stabilization of all disturbed areas, the Contractor shall dismantle the remaining temporary erosion and sediment control elements. The contractor shall remove any unsuitable material from the site left from the erosion and sediment control measures. The disturbed areas, following removal of the temporary measures, shall be stabilized with permanent vegetation. When all construction is complete, temporary measures have been removed, and vegetation is established, Hamilton County SWCD must complete a final release inspection. The contractor shall file a Notice of Termination (NOT) with the IDEM, submit a copy to the Hamilton County SWCD, and complete all other required NOT actions in accordance with INDOT Construction Memorandum 16-02.

B-15 Erosion and sediment control specifications for individual building lots: Not applicable.

#### Stormwater Pollution Prevention Plan - Post Construction Component (Section C)

- Description of pollutants and their sources associated with the proposed land use:

  Additional pollutant sources will be from trash (both organic and inorganic), lawn chemicals, grass clippings, grit brought in from the existing surrounding roads from various vehicles (fuel, antifreeze, oil, grease, brake dust, brake fluid, transmission fluid, other hydrocarbons, etc.), pet and other animal waste, etc.
- $\lfloor C-2 \rfloor$  Sequence describing stormwater quality measure implementation:

Upon completion of all bridge and road work most of the site will be paved. Shoulders, ditches and other disturbed areas will be seeded, mulched or sodded to develop vegetative filter strips. Slopes directly under the new bridge will be protected with rip rap. All existing vegetation outside of the project limits will not be disturbed, and this vegetation will continue to filter out pollutants from the stormwater prior to it leaving the site, and entering into the surrounding water sources.

 $\boxed{\text{C}-3}$  Description of proposed post construction stormwater quality measures:

needed, based on regular inspections by the appropriate government agency.

The above referenced measures will serve as filtering measures, to reduce the amount of pollutants contained within the stormwater as it leaves the project site. Additionally, the measures will serve to reduce the amount of erosion within the project site, thus reducing the amount of sediment within the stormwater.

C-4 Location, dimensions, specifications and construction details of each stormwater quality measure:

The entire project site will be seeded in accordance with Construction Component "Section B" of this Storm Water Pollution

Prevention Plan.

C-5

Description of maintenance quidelines for proposed post-construction water quality measures:


Erosion and sediment control: Repair and revegetate eroded areas in the project site. These measures will be implemented, as


Other maintenance shall be in accordance with Hamilton County standard operating procedures following construction in regards to inspections, mowing and right-of-way maintenance, debris and litter removal, nuisance control, sediment removal, and necessary repairs.

	RECOMMENDED FOR APPROVAL	B. K.	hlis	DESIGN ENGINE	04/28, ER	/2017 DATE	
	DESIGNED:	BSS		DRAWN:	DJG		
HILL	CHECKED:	ВКА		CHECKED:	BSS		

LIABATI TONI COLINITY	HORIZONTAL SCALE	BRIDGE FILE				
HAMILTON COUNTY	1"=20'	HAMILTON CO. BR. 306				
HIGHWAY DEPARTMENT	VERTICAL SCALE	DESIGNATION				
	N/A	PB-14-0004				
TEMPORARY EROCION CONTROL	SURVEY BOOK	SHEETS				
TEMPORARY EROSION CONTROL		13 of 39				
INFORMATION SHEET	CONTRACT	PROJECT				
THE OIL WITTON STILL		PB-14-0004				

Date: May 25, 2017, 9:55am User Name: bstutzman File: M:[\_2014|214-0030|Road|C4D|Erosion|Temp Erosion Control.dwg





<u>LEGEND</u>

Line, Multi-Component, Solid, White, 4 IN.

45) Line, Multi-Component, Solid, Yellow, 4 IN.

No. 19800103  STATE OF  ADIANA  ANDIANA  ANDIANA
MAL LIMINI

RECOMMENDED FOR APPROVAL	B: K And	DESIGN ENGINEER	04/28/2017 DATE	
DESIGNED:	BSS	DRAWN:	DJG	
CHECKED:	ВКА	CHECKED:	BSS	

LIANATI TONI COLINITY	HORIZONTAL SCALE	BRIDGE FILE				
HAMILTON COUNTY	1"=20'	HAMILTON CO. BR. 306				
HIGHWAY DEPARTMENT	VERTICAL SCALE	DESIGNATION				
	N/A	PB-14-0004				
	SURVEY BOOK	SHEETS				
PAVEMENT MARKING AND SIGNING		15	of	39		
STA. 61+00.00 TO STA. 67+00.00	CONTRACT	PROJECT				
51A. 01 100.00 10 51A. 07 100.00		PB-14-0004				

EARTH EXPLORATION &	LOG OF TEST BORING  Project Small Structure 23034 Improvements Location Hamilton County, Indiana Client Lochmueller Group, Inc. 7770 West New York Street — Indianapolis, Indiana 317—273—1690 / 317—273—2250 (Fax)	Elev Dat EEI	ring No. TB-1 Protion 834 tum NAVD 88 I Proj. No. 1-15-401 eet 1 of 2		ARTH XPLC	ORATION'S	Project Location Client	LOG OF TEST BORING  Small Structure 23034 Improveme Hamilton County, Indiana Lochmueller Group, Inc.  New York Street — Indianapolis, Indiana 41 517—273—1690 / 317—273—2250 (Fax)		Boring N Elevation Datum EEI Proj. Sheet	834 NAVD 88		EARTH EXPLO	PATION'E	Project Location Client 7770 V	LOG OF TEST BORING  Small Structure 23034 Improveme Hamilton County, Indiana Lochmueller Group, Inc.  West New York Street — Indianapolis, Indiana 317—273—1690 / 317—273—2250 (Fax)	ents Ele	oring No. levation atum El Proj. No. heet 1	83 NAVD	TB-2 334 /D 88 5-401 f 1
Project No Struct. No. Hamilton SS 2303	Station 59+25 Weather 64 Offset 6 ft Rt. "A" Temp.	Sunn 80°		Project Struct		 Hamilton SS 230	Station 34 Offset	59+25 Weathe 6 ft Rt. "A" Temp.		Sunny 80° F	Driller B.J. Inspector	Projec Struct	et No. I. No. I	 Iamilton SS 230	Station 34 Offset				Oriller nspector	B.J. 
SAMPLE	DESCRIPTION/CLASSIFICATION		SOIL PROPERTIES		SAM	(PLE	DESC	RIPTION/CLASSIFICATION		SOIL	PROPERTIES		SAM	PLE	DE	SCRIPTION/CLASSIFICATION		SOIL P	ROPER	RTIES
No.   Rec   N Depth   Y Value   ft   Ele	and REMARKS	q <sub>p</sub> tsf	qu Ya W LL Pl	PI No.	T Rec	N Depth Value ft	Elev	and REMARKS	c t	գ <sub>թ</sub> գլ	γ <sub>α</sub>	PI No.	T Rec	N Depth Value ft E	lev	and REMARKS	q <sub>p</sub> tsf	գս tsf	γ <sub>d</sub> ∗pcf	
-	ASPHALTIC CONCRETE, 11 in.					-	0									TIC CONCRETE, 10 in. AR SUBBASE (visual)				
SS-1 90 7 _	SILTY CLAY LOAM, very stiff, brown	2½	25.1	SS-11	90	39 - 80	0-1°°°°					SS-1	90	9 -	11111	very stiff, brown (possible fill)	21/2			14.4
00 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0						35	SAND AND	GRAVEL, dense, wet, gray					$\frac{1}{M}$	4 830	-     -					
SS-2   90   4   5   5	SANDY LOAM, very loose, moist, brown					-						SS-2	90	5		.OAM, medium stiff, dark gray	1	+	;	37.3
SS-3 X 90 21 T					$\downarrow \downarrow \downarrow$		_ •					SS-3	90	13	<del>                                     </del>					
	SAND, medium dense, moist to wet, brown			SS-12	90	43 73	1							▽ ▼	SANDY	LOAM, medium dense, moist				
SS-4 90 15 - 825-	] o` . ], ` . · q					-						SS-4	90	12 - 825						
						SANDY LOA	SANDY LOAM, dense to medium dense, wet,				<u> </u> 									
SS-5   90   21   _	GRAVELLY SAND, medium dense, wet, gray			SS-13	SS-13 90 28 790		High occasional sand seams				SS-5	90	12							
SS-6 V 90 23 820-	]											SS-6	90	13 820	TO CRAVEL	LY SAND, medium dense to very		+	$\rightarrow$	
15	] · · · d   · · ·					F	-1111							15		Wet, gray				
SS-7 90 25	† : ` .   	AV	9.7	SS-14	55	50/.5 - 78				3	14.1	SS-7	90	14						
-	1         -           -	4½	9.7			-50	1111								1 × 1 1 × 1					
S-8 90 41 - 815-		>4½	9.5	Ш		Ē						8-22	90	61 - 815						
	<u> </u>							, hard, brown, possible cobble or						<u>-</u>	•   					
	-     -     LOAM, hard to very stiff, gray, with sand seams			SS-15	90	69 - 78	boulder ne	or 48 ft	>-	-41/2	11.1			-	<u> </u>					
SS-9 X 90 32 - 810-	below 29 ft	>4½	10.2			-	<del> </del>					SS-9	90	60 - 810	<u>-</u>		>41/2			10.4
25	<u>:</u>			$\Box$		E									- - - - - - - - - - - - - - - - - - -	hard, gray		+ +		
	<u>-</u>			SS-16	105	82/0.9 - 77	SANDY LOA	M, very dense, wet, brown, with						<u>-</u>	<u>-</u>					
905	<u> </u>					<b>—60</b>	wet sand						M	- 805	<u> </u>			+		
SS-10 X 90 39 5 805-		3	13.4	$\coprod$				End of Boring at 60 ft< <c>&gt;</c>				SS-10	90	50 - 30	1111		>4½			9.6
	SAND AND GRAVEL, dense, wet, gray						Boring adv	anced from 30 to 60 ft on 12/21,	/15							End of Boring at 30 ft< <c>&gt;</c>				
WATER	Continued Next Page LEVEL OBSERVATIONS	GE	NERAL NOTES											WATER	LEVEL OBS	SERVATIONS	Gl	ENERAL	NOTES	<u> </u>
Depth ∑ Whi ft Drill	ile ▼ Upon ♀ Start	9/21/15	End 9/21/15 Rig CME 7	<b>i</b>									Depth	∑ W∤ Dril	nile <u>¥</u>		art 9/21/15	End .9/	21/15 F	Rig CME 75
To Water89	т пришив		3¼" I.D. HSA Truck illed with auger cuttings,										 Γο Water	ווזט 8	ииу <u>%</u>	יוטן י	illing Method marks Back	3¼" I. afilled with a	.D. HSA auger cutt	Truck Hings,
To Cave-in	<u>22½</u> bentonite	chips an	nd concrete patch at surface.	The state the tr	tratification ansition ma	lines represent th by be gradual.	approximate boundar	y between soil/rock types and		·		Т	Γο Cαve−i		approximate bou	13½	ntonite chips a	and concrete	patch at	ot surface.
ne transition may be gradual.	approximate boundary between soil/rock types and											the tro	consition ma	/ be gradual.	Abhi ovuninia 2000	ındary between soil/rock types and				<u> </u>

RECOMMENDED FOR APPROVAL Of am Same DESIGN ENGINEER

MAR

DESIGNED:

CHECKED:

No. 11400165

STATE OF

WOJANA

WOJANA

STATE OF

04/28/2017 DATE

ACS

CHECKED:

# PILE LOADING FOR GEOTECHNICAL TESTING

	BENT #1	BENT #2		
Pile Size, Type & Grade	SEC 14x0.312, Gr.42	SEC 14x0.312, Gr.42		
Factored Design Load	160 kip	160 kip		
Factored Design Soil Resistance	160 kip	160 kip		
Resistance Factor for Axial Compression	0.55	0.55		
Downdrag Loads	0	0		
Nominal Soil Resistance	291 kip	291 kip		
Downdrag Friction	0	0		
Scour Zone Friction	0	0		
Relaxation of Tip in Shale	N/A	N/A		
Nominal Driving Resistance	291 kip	291 kip		
Estimated Pile Tip Elevation	801.00	801.00		
Testing Method	INDOT Standard Specification 701.05(a)*			

\*\* Restrike Of Piles Shall Be Performed After a Waiting Period of 2 Days After The Initial Drive.

LEGEND OF SAMPLE TYPES


SS-Split Spoon

RC-Rock Core

ST-Shelby Tube

HORIZONTAL SCALE BRIDGE FILE HAMILTON COUNTY HAMILTON CO. BR. 306 1"=10' HIGHWAY DEPARTMENT VERTICAL SCALE DESIGNATION PB-14-0004 1"=10' SHEETS SURVEY BOOK of PROJECT SOIL BORINGS CONTRACT PB-14-0004

_	٦.
$\boldsymbol{\omega}$	Plans soil_
10	`≅
	<u>8</u>
~	<u>v</u>
	<u>~</u>
w.	22
=	≈
≥	Plai
Ų.	σ.
<	
	Ω.
₹.	8
אַ	8
₹	J
J	<u> </u>
	w
2	0
ς.	0
Q	·E
20.	<u> </u>
ヾ	<u> ~</u>
	$\overline{c}$
V	≈
Ni.	~
•	$\geq$
``	214-0030 Bridge
	4
7	7.
_	7
V	$\sim$
- 2	_
<del>,</del>	4
₹.	7
4	0
~	N
Œ,	٦.
€	_
ite: May 24, 2017, 12:38pm User Name: trac)	e: S:\_2014\214
٠.	S
ai	
ಽ	à
~	



# STRUCTURE TO BE BUILT TO A 240' VERTICAL CURVE

# **DESIGN STRESSES**

TYPICAL ROAD CROSS SECTION

See Sheet Nos. 4 & 5

Class C Concrete: f'c= 4,000 psi Reinforcing Steel (Grade 60): fy= 60,000 psi

#### **DESIGN DATA**

The Bridge is Designed for HL-93 Loading. Loading in Accordance with AASHTO LRFD 7th Edition, 2014

Specifications & Interims thru 2015.

Actual Weight Plus 35 lbs/ft For Future Wearing Surface

Designed with a 1/2" Sacrificial Wearing Surface.

#### SEISMIC DATA

AASHTO LRFD Bridge Design Specifications with Interims.


Seismic Design Category 1

S1-0.0479

Site Class D Fv = 2.40

#### **GENERAL NOTES**

- 1. Reinforcing Steel Covering Shall Be 2" Unless Noted Otherwise.
- 2. Chamfer Exposed Edges 1" Unless Noted.
- 3. Concrete Requirements: Concrete in Superstructure to be Class "C".



Shldr.

3/4" Half Round (Typ.)

32'-6" O. to O. Coping

32'-0" Clear Roadway

TYPICAL CROSS SECTION SCALE: 5/16" = 1'-0"

Lane

12'-0"

Lane

#### RIPRAP & GEOTEXTILE QUANTITIES

	BENT #1	BENT #2
Geotextiles	213 yd <sup>2</sup>	213 yd
Class 1 Riprap	223.5 Tons	223.5 Tor
Revetment Riprap	40.5 Tons	40.5 Ton

#### END BENT BACKFILL QUANTITIES

	BENT #1	BENT #2
Structure Backfill, Type 3	106 yd <sup>3</sup>	107 yd <sup>3</sup>


### END BENT EXCAVATION QUANTITIES

	DEINI #1	DEINI #Z
Excavation, Common	135.5 yd <sup>3</sup>	135.5 yd <sup>3</sup>
Excavation, Foundation, Unclassified	129.6 yd <sup>3</sup>	133.8 yd <sup>3</sup>

# CYNTHEANNE ROAD OVER FRANK KEISER DRAIN REINFORCED CONCRETE SLAB BRIDGE

1 SPAN @ 27'-0" CLEAR ROADWAY: 32'-0" SKEW: 25°00'00" LT.

SHEETS of PROJECT PB-14-0004



Railing, Type TS-1


\_\_(Typ.)

ECOMMENDED DR APPROVAL	Odam	Stewn	DESIGN ENGINEER	04/28	/2017 DATE	
SIGNED:	ACS		DRAWN:	TAM		
IECKED:	CRF		CHECKED:	ACS		

LIANATI TONI COLINITY	HORIZONTAL SCALE	BRIDGE FILE
HAMILTON COUNTY	3/16"=1'-0"	HAMILTON CO. BR. 306
HIGHWAY DEPARTMENT	VERTICAL SCALE	DESIGNATION
	3/16"=1'-0"	PB-14-0004
	SURVEY BOOK	SHEETS
GENERAL PLAN		18 of 39
GENERAL PLAN	CONTRACT	PROJECT

VERTICAL CURVE INFORMATION

Shldr.




NOTE: Proposed Piles are Steel Pipe, 14" Ø x 0.312" Piles.
Piles Shall be Driven to Nominal Driving
Resistance Shown in Table on Sheet 16.
Conical Pile Tips are Required.

PLAN VIEW

No. 11400165	RECOMMENDED FOR APPROVAL	Odam	Stury	DESIGN ENGINEER	04/28/2017 DATE	
STATE OF WOTANA	DESIGNED:	ACS		DRAWN:	TAM	
THE STONAL ENGLISHED	CHECKED:	JRG		CHECKED:	ACS	

LIABATI TONI COLINITY	HORIZONTAL SCALE	BRI	DGE FILE	Ξ
HAMILTON COUNTY	5/16"=1'-0"	HAMILTO	N CO. B	R. 306
HIGHWAY DEPARTMENT	VERTICAL SCALE	DES	IGNATIO	N
	5/16"=1'-0"	PB-	14-0004	1
	SURVEY BOOK	9	HEETS	
FOUNDATION LAYOUT		19	of	39
FOUNDATION LATOUT	CONTRACT	P	ROJECT	
		PB-	14-0004	1



No. 11400165

STATE OF

WOJANA

WOJANA

STATE OF

ACS

JRG

TAM

ACS

CHECKED:

END BENT #1 & #2 CONSTRUCTION

DESIGNED:

CHECKED:

BRIDGE FILE

DESIGNATION

PB-14-0004

SHEETS

of

PROJECT


PB-14-0004


20


1/4"=1'-0"


SURVEY BOOK


CONTRACT














ACS

CHECKED:

ACS

CHECKED:

PROJECT

PB-14-0004

CONTRACT

											SU	MMARY	OF BI	RIDGE	QUAI	ITITI	ES													
			CONCRETE			DATI INC		REINF.		CHARDRAII	THREADED	REINF. CONC.	DENCE			PIPE,		CTDUCTUR	_				PILES				Е	XCAVATION		
ITEM		ASS C R SUBSTR	CLASS A SUBSTR	ABOVE FTG.	ISS B IN FTG.	RAILING, CONCRETE, PF-2	REINF. BARS	BARS, EPOXY COATED	RAILING, TS-1	GUARDRAIL TRANSITION, TGS-1	TIE BAR ASSEMBLY, E.C.	REINF. CONC. BRIDGE APPROACH (10 IN.)	DENSE GRADED SUBBASE	REVETMENT RIPRAP	CLASS 1 RIPRAP	END BENT DRAIN, 6 IN.	GEOTEXTIL	STRUCTURE BACKFILL, TYPE 3	STEE 14"ø	PIL	YNAMIC LE LOAD TEST	TEST PILE, INDICATOR, PRODUCTION	TEST PILE, INDICATOR, RESTRIKE	CONICAL PILE TIPS	STE CON	EEL H, REINF. NC. ENCASED (HP 12x53)	FOUNDATION, UNCLASSIFIED	COMMON	DRY	SURFACE SEAL**
	CYS	CYS	CYS	CYS	CYS	CYS	LBS	LBS	LFT	EACH	EACH	SYS	CYS	TON	TON	EACH	SYS	CYS	NO.	LFT I	EACH	LFT	EACH	EACH	NO.	LFT	CYS	CYS	CYS	SFT
BENT #1		80.4						12081			36			40.5	223.5		213	106	8	242		41	1	9			129.6	135.5		
BENT #2		80.4						12081			36			40.5	223.5		213	107	8	242		41	1	9			133.8	135.5		
CURENCERLICEURE	70							10050	44																					1050
SUPERSTRUCTURE	78							10958	44	4																				1050
R.C. BRIDGE APPROACH								11028				202.4	33.2																	1820
TOTALS	78	160.8						46148	44	4	72	202.4	33.2	81	447		426	213	16	484		82	2	18			263.4	271		2870

<sup>\*\*</sup> ESTIMATED QUANTITY LUMP SUM ITEM

No. 11400165

STATE OF

NODIANA

NODIANA

STONAL ENGINEERING

 RECOMMENDED FOR APPROVAL	Odam	Stavy DESIGN ENGINEER	04/28/2017 DATE	
DESIGNED:	VCH	DRAWN:	VCH	
CHECKED:	ACS	CHECKED:	ACS	

TAIDTANIA	HORIZONTAL SCALE	BRI	DGE FIL	E	
INDIANA	NONE	HAMILTO	N CO. E	3R. 306	
DEPARTMENT OF TRANSPORTATION	VERTICAL SCALE	DES	IGNATIC	N	
	NONE	PB-	-14-000	4	
	SURVEY BOOK	9	SHEETS		
BRIDGE SUMMARY OF QUANTITIES		27	of	39	
DRIDGE SUMMART OF QUANTITIES	CONTRACT	Р	ROJECT		
		PB-14-0004			

												GUA	RDRAIL	SUMM	ARY T	ABLE									
	LOCATION					W	/-BEAM G	GUARDRA	IL LENG	ТН		<u> </u>	NO	NOI		4ENT	CURVE		am Guaf Tem	RDRAIL	111		YPE	YPE	
FROM STATION	TO STATION	LEFT	MEDIAN LEFI	RIGHT STANDARD POST AT 6		STANDARD POST AT 3 FT 1.5 IN. SPA.	DOUBLE FACED AT 6 FT 3 IN. SPA.	DOUBLE FACED AT 3 FT 1.5 IN. SPA.		SHOP CURVED AT FT. SPA.	NESTING GUARDRAIL	GUARDRAIL FLARE RATE	GUARDRAIL TRANSITION TYPE TGS-1	GUARDRAIL TRANSITI		GUARDRAIL END TREATMENT TYPE OS	TERM SYS <sup>-</sup>			ECTOR STEM	GUARDRAIL REMOVE	GUARDRAIL RESET	IMPACT ATTENUATOR T	IMPACT ATTENUATOR T	REMARKS
				LF	FT	LFT	LFT	LFT	LFT	LFT	EACH		EACH	EACH		EACH	TYPE	EACH	TYPE	EACH	LFT	LFT	EACH	EACH	
58+98.29	59+10.79	Х		12	2.50								1			1									
58+38.21	59+25.71			X 87	7.50								1			1									
59+70.29	60+07.79	X		37	7.50								1				4	1							
59+85.21	61+91.46			X 206	6.25								1			1									
TOTALS				34	14.0								4			3		1							

									SHEET	SIGN &	POST SU	IMMARY							
					SIG	SN								POST	Γ				
									MOUNTED ON		U CH	ANNEL				SQUARE			
PLAN SHEET	SIGN LOCATION	SIGN	SIG	SN S	IZE	GROUND - MOUNTED   PANEL				POST LENGTH POST LENGTH		POST LENGTH		2" X 2	2" - 12 GA. (T	2 1/4" X 2 1/4" - 12 G/ (TYPE 1)			
NO./	(STA.)	CODE	(II	١x١	N)				/ ( <u>. c=</u> /					REI	NFORCED AND	CHOR	REINFORCED ANCHO		
LINE	(31/11)					0.000"	0.100"	0.125"	0.000"	1	2	TYPE "A"	TYPE "B"	PC	FT.)	POST LENGTH (FT			
						0.080"	0.100"	0.125"	0.080"	FT.		FT.	FT.	1	2	TOTAL	1	TOTAL	
Line "A"	58+00.00	W8-13	36		36		9.00										11.0	11.0	
1	61 . 00 00	W0 12	26	Х	26		0.00										11.0	11.0	
Line "A"	61+00.00	W8-13	36	x	36		9.00										11.0	11.0	
				×															
				х													<u> </u>		
				х															
				х															
				х															
				X															
				x Total			18.00										+	22.00	

							חאיירם	CIDE	NTC!!			II ANIT		TNIC C		V TADI	_					
				-			PAVED				PDITC	H, ANL				Y IABL						
	LOCATION							AVED SI	DE DITCH	<u> </u>				PRAP DIT	CH		EROS1	ION CON	TROL BLA			Ì╞││
					ENGTH	VALLS LENGTH )	LENGTH )	TOTA	AL EQUI\	TYPE	PAY LENC	STHS	RIPRAP	ZM P	TLES	SIDE ES	CHES	OIAN	SHOULDER BREAK	BRIDGE	SODDING	ORCEME!
FROM STATION	TO STATION		MEDIAN	RIGHT	ACTUAL LENGTH	CUT OFF WALLS (8' EQUIVAL. LENGTH EACH)	LUGS (8' EQUIVAL. L EACH)						REVETMENT	UNIFORM RIPRAP	GEOTEXTILES	FOR PAVED SIDE DITCHES	FOR DITCHES	FOR MEDIAN	FOR SHOU BREA	SODDING AT E CONE	TOTAL SOI	TURF REINFORCEMENT MAT
					LFT	EACH	EACH	LFT	LFT	LFT	LFT	LFT	TONS	TONS	SYS	SYS	SYS	SYS	SYS	SYS	SYS	SYS
51+00.00	56+10.00			Х	510.00												453					
56+10.00	59+48.00	Х			338.00												451					
56+10.00	57+33.50			Х	123.50												110					
59+48.00	65+50.00	Х			602.00												535					
62+40.00	64+00.00			Х	160.00												142					
64+50.00	65+50.00			Х	100.00												89					
			T																			
64+00.00	64+50.00			Х	50.00																	28
64+50.00	65+50.00			Χ	100.00												1700					
	TOTAL																1780					28

	R/W MARKE		
Line	Station	Offs	et T
A	51+25.00	45.00	LT
A	53+35.00	45.00	LT
A	55+80.00	90.00	LT
Α	59+76.00	90.00	LT
A	62+35.00	45.00	LT
A	65+20.00	45.00	LT
Α	52+15.00	60.00	RT
A	55+25.00	60.00	RT
A	55+50.00	65.00	RT
A	56+75.00	65.00	RT
A	57+00.00	60.00	RT
A	64+00.00	60.00	RT

		MAILBOX APF	PROACHE	S		
LT./RT.	C/L BOX	DESCRIPTION	WIDTH,	ASS	SEMBLY RE	Q'D
21.,1011	STATION	DESCRIPTION	W(FT)	SINGLE	DOUBLE	
LT	53+86			X		
LT	57+52			X		
LT	63+10			X		
		TOTAL		3		

		SURVE	Y MONU	MENT	TABLE		
CTATION	LINE	OFFCET	SECTION		TY	PE	
STATION	LINE	OFFSET	CORNER	Α	В	С	D
51+50.00	Α	0.0			Х		
60+53.59	Α	0.0	Х				
64+00.00	Α	0.0			Х		
	TOTALS		1		2		

MINIMUM ARTERINA
ARTERIAL ARTERIAL
P QEGISTERED
ARTERION ARTERION No. 19800103 STATE OF WOLANA COMMINISTRATION OF STATE OF WOLANA COMMINISTRATION OF STATE OF S
STATE OF
WOLANA W
WOLANA W

	RECOMMENDED FOR APPROVAL	B: K Bu	DESIGN ENGINEER	04/28/2017 DATE	H
	DESIGNED:	BSS	DRAWN:	DJG	
·	CHECKED:	ВКА	CHECKED:	BSS	

LIANATI TONI COLINITY	HORIZONTAL SCALE	BF	RIDGE	FILE	
HAMILTON COUNTY	3/8"=1'-0"	HAMILTO	N CO	. BR. 306	6
HIGHWAY DEPARTMENT	VERTICAL SCALE	DES	IGNAT	ION	
	N/A	PB-	14-00	004	
	SURVEY BOOK	S	HEET	5	
DOAD CLIMMADY		28	of	39	١
ROAD SUMMARY	CONTRACT	PI	ROJEC	Τ	
		PB-	14-00	004	

						PAVEMENT QUANTITIES AND APPROACH TABLE																												
					W LINE	SURFAC	E BEYO	ND R/W							ORIVE						1A MATERIALS	, , ,	r, TYPE I	, TYPE IC	, TYPE III	НМ	ИА МАТЕ	RIAL FO	PR:			CC	MPACTED	
LOCATION	DESCRIPTION (APPROACH TYPE OR CLASS)	HTQIW	T	지 RADII	그 DISTANCE BEYOND R/	COMPACTED AGGREGATE, NO. 53	SYS	SCONCRETE	1 %	GR 2 %	ADE  3  %	4 %	EXCAVA CUT CYS	FILL CYS	디 CLEAR ZONE AT D	HMA FO	LB		MOL NOL 885 193 (A) 282 (A) SURFACE, 64, SURFACE, 65, SURFACE, 65, SURFACE, 66, SUR	LI	OC/QA HMA, 2 OC/QA	QC/QA HMA, 2, QC/QA HMA, 2, 64, BASE, 25mm	SUBGRADE TREATMEN	SUBGRADE TREATMENT	SUBGRADE TREATMENT	기OINT SEALANT, SURFACE	기OINT SEALANT, INTERMEDIATE	LIQUID ASPHA LT SEALA NT	TACK COAT	SYS	DEPTH 6" TON SYS	V	GREGATE NO. 53 ARIABLE DEPTH	REM.
51+00 to 51+50	Mainline	Varies	50.0																10.3		17.1	20.5		124.4		50.0	50.0	50.0	0.06	124.4	41.4			
51+50 to 52+50	Mainline	24	100.0																22.0		36.7	44.0		266.7		100.0	100.0	100.0	0.13	266.7	88.8			
52+50 to 57+88.21	Mainline	24	538.2																118.4		197.3	236.8	1435.2			538.2	538.2	538.2	0.72	1435.2	477.9			
57+88.21 to 58+48.29	Mainline	28	60.1																15.4		25.7	30.8	186.9			60.1	60.1	60.1	0.09	186.9	62.2			
58+48.29 to 59+05.44	Mainline	32	57.2																16.8		27.9	33.5	203.2			57.2	57.2	57.2	0.10	203.2	67.7			
59+90.56 to 60+07.79	Mainline	32	17.2																5.1		8.4	10.1	61.2			17.2	17.2	17.2	0.03	61.2	20.4		$\perp$	
60+07.79 to 62+41.46	Mainline	28	233.7														-		60.0		100.0	120.0	727.1			233.7	233.7	233.7	0.36	727.1	242.1			
62+41.46 to 62+50.00	Mainline	24	8.5																1.9		3.1	3.8	22.8			8.5	8.5	8.5	0.01	22.8	7.6			
62+50 to 64+00	Mainline	24	150.0																33.0		55.0	66.0		400.0		150.0	150.0	150.0	0.20	400.0	133.2			
64+00 to 65+50	Mainline	Varies	150.0																29.8		49.7	59.7		362.5		150.0	150.0	150.0	0.18	361.7	120.4			
51+00 to 51+50	Mainline	Varies	50.0																					33.3								33.3	3 18.1	
51+50 to 52+50	Mainline	8	100.0																					88.9								88.9	48.2	
52+50 to 57+88.21	Mainline	8	538.2																				478.4									478.	4 259.1	
57+88.21 to 58+48.29	Mainline	7.5	60.1																				50.1									50.:	27.2	
58+48.29 to 59+05.44	Mainline	7	57.2																				44.5									44.!	5 24.1	
59+90.56 to 60+07.79	Mainline	7	17.2																				13.4									13.	7.3	
60+07.79 to 62+41.46	Mainline	7.5	233.7																				194.8									194.	8 105.5	
62+41.46 to 62+50.00	Mainline	8	8.5																				7.6									7.6	4.2	
62+50 to 64+00	Mainline	8	150.0																					133.3								133.	3 72.2	
64+00 to 65+50	Mainline	Varies	150.0																					100.0								100.	0 54.2	
54+11	Class II Drive	11	48	25/15												78.9	7	7.0	15.0						78.9								$\perp$	
57+41	Class II Drive	12	49.1	25/15	20.9	7.1										84.4	7	7.0	16.0						84.4								7.1	
60+39	Class V Drive	24	53	25/15												150.9																	36.7	
63+25	Class II Drive (Mod.)	12	33.2	15/15	30.8	9.1										56.3	5	5.0	11.0						56.3								9.1	
Additional aggregate for e	xtending to slope every 100'																	$\perp$															3.6	
Around guardrail end section	ns																																22.4	
TOTAL																	1	19	42 313		522	626	3426	1510	220	1365	1365	1365	2		1262	+	699	
	1	1	1	ī	1	1				1	1	,	<u>.                                    </u>	L								1							1	1	<u> </u>			

ARTERIS HOLLING TO STATE OF A TOUR AND A STATE OF A TOUR AND A TOU

	RECOMMENDED FOR APPROVAL		DESTGN ENGINEER	04/28/2017 DATE	- 11
	DESIGNED:	CCW	DRAWN:	DJG	-
, ·	CHECKED:	ВКА	CHECKED:	BSS	

LIANATI TONI COLINITY	HORIZONTAL SCALE	BRI	DGE F	ILE
HAMILTON COUNTY	3/8"=1'-0"	HAMILTO	N CO	. BR. 306
IIGHWAY DEPARTMENT	VERTICAL SCALE	DES	IGNAT	TON
	N/A	PB-	-14-00	004
AN /ENACNIT OLIANITITIC	SURVEY BOOK	S	SHEET:	S
PAVEMENT QUANTITIES		29	of	39
AND APPROACH TABLE	CONTRACT	P	ROJEC	T
THE THIRD TOTAL		PB-	-14-00	004

																S	TRUCT	JRE DAT	TA TABLE															
1BER		LO	CATION			DES	CRIPTION	т	:CTION H		FLOW LIN	NE	IFE .	NOI		ТНОБ	ACKFILL		CKFILL		.LES	RIPRAP		SCOUR PROT	ECTION		SS A, FOR	CTION	CTION				Ä.	
STRUCTURE NUM	STATIC	DN FF	RIGHT	OFFSET	SIZE	CATO	NHOLE, INLET, CH BASIN, OR SPECIALTY RUCTURE AND TYPE	LENGT	VIDEO INSPE LENGTH	SKEW	UP STREAM	DOWN STREAM	SERVICE	SITE DESIGNAT	pН	BACKFILL MET	STRUCTURE B,	TYPE	FLOWABLE BA	TYPE	GEOTEXTI	REVETMENT I	SUMP DEPTH	GEOTEXTILE	avadra		CONCRETE, CLA	VIDEO INSPE	BIPE END SE	ATED BO	OX END SAFETY META ON SECTION		CONNECT TO S	REMARKS
				FT	IN.			LFT	LFT	LFT	ELEV.	ELEV.	YRS				CYS		CYS		SYS	TON	IN.	SYS	TYPE	TONS	CYS	LFT	EA TYP	E SLO	PE EA. TYPE SLOPE	EA.		
					1						222.47	001.71			7																			
11	54+11.0	00	X	36.7	15	3	Culvert	30.0		4.1	832.17	831.71	75		/		2.7	2											2					
12	56+10.0	00	Х	0.0	60	1	Culvert	62.0		5.1	828.58	827.86	75		7		144.4	1			125.9	94.4												2 Concrete Anchors
14	60+39.0	00 X		49.6	15	3	Culvert	41.0		6.7	832.91	831.58	75		7		4.7	2											2					
15	62.50.0	0 /		27.0	1.5		Inlet Type A-2	41.0		4.7	020.22	027.02	75		7																			
15	63+50.0	U X		37.0	15	3	Tillet Type A-2	41.0		4.7	838.23	837.82	75		/		4.1	2											1					
																																+ + +		
	Total																				125.9	94.4							5					

							PIPE MATERIAL TABLE			
							STRUCTURE NUMBER			
			11	12	14	15				
	PIPE TYPE / SHAPE		3 / Circular	1 / Circular	3 / Circular	3 / Circular				
	SMOOTH PIPE SIZE		15	60	15	15				
	CORRUGATED PIPE SIZE		15	60	15	15				
	RCP/RCHEP (S)  CLASS D 0.01 RAT		1000	1000	1000	1000				
	NON-REINFORCED CONCRETE PIPE, CLASS 3		1000 X	1000	1000 X	1000 X				
	CORRUGATED PE PIPE, TYPE S (S)*	, (0)	X		$\frac{1}{x}$	X				
	RIBBED PE PIPE (S)*									
	SMOOTH WALL PE PIPE (S)* / MAXIMUM D	DR .	X / 26		X / 26	X / 26				
	PROFILE WALL PVC PIPE (S)		Х		X	Х				
	SMOOTH WALL PVC PIPE (S)*		Х		X	X				
	VITRIFIED CLAY PIPE, EXTRA STRENGTH (	•	X		X	X				
	FULLY BIT. PAVED & LINED (S)	CORR. PROFILE THICKNESS		1	1	+		<del></del>	<del>                                     </del>	
		CORR. PROFILE		2 2/3" x 1/2"	1					
	ZINC COATED (C)	THICKNESS		0.168	1			1	<u>LEGEND</u>	
		CORR. PROFILE	2 2/3" x 1/2"		1					
뜻	ZINC COATED W/ BPI (C)	THICKNESS	0.109	0.109	0.109	0.109		RCP-	Reinforced Concrete Pipe	
🔻		CORR. PROFILE	2 2/3" x 1/2"		RCHEP-		ie.			
H	ALUM. COATED TYPE 2 (C)	THICKNESS	0.109	0.109	0.109	0.109		PE-	Polyethylene	J
፟		CORR. PROFILE	0.103	0.103	0.105	0.103		DR-	Dimension Ratio	
<u>H</u>	ALUM. COATED TYPE 2 W/ BPI (C)							-		
=		THICKNESS						PVC-	Polyvinyl Chloride	
	POLYMER PRECOATED GALVANIZED (C)	CORR. PROFILE	2 2/3" x 1/2"		BIT-	Bituminous				
STI	1 0211121(11120071122 071271112225 (0)	THICKNESS	0.109	0.109	0.109	0.109		CORR-	Corrugation	
ED	POLYMER PRECOATED GALVANIZED W/ BPI (C)	CORR. PROFILE						BPI-	Bituminous Paved Invert	
<del> </del>	TOZITIZIONI ZO GIZINI IZZZO WI DI Z (G)	THICKNESS						ALUM-	Aluminum	
	POLYMER PRECOATED GALVANIZED CORRUGATED STEEL PIPE	CORR. PROFILE		2 2/3" x 1/2"				STR-	Structural	
)   	TYPE 1A (S)	THICKNESS		0.109				CFP-	Concrete Field Paving	
8	FIBER BONDED BITUMINOUS COATED (C)	CORR. PROFILE						CIR-	Circular Pipe	
	TIBER BONDED BITOMINOUS COATED (C)	THICKNESS						DEF-	Deformed Pipe	
	FIBER BONDED BITUMINOUS COATED W/ BPI (C)	CORR. PROFILE						(S)-	Smooth Pipe Material	
	11521(5611525 521611211665 6611125 11, 511 (6)	THICKNESS						(C)-	Corrugated Pipe Material	
	CORRUGATED ALUM. ALLOY PIPE (C)	CORR. PROFILE	2 2/3" x 1/2"		OK-	Acceptable for Use				
	CORROGATED ALON. ALLOT FIFE (C)	THICKNESS	0.06	0.135	0.06	0.06		(LS)-	Lock Seam Pipe Required	
	CORRUGATED ALUM. ALLOY PIPE W/ BPI (C)	CORR. PROFILE						1		
	CORROGATED ALOM. ALLOT FIFE W/ DFI (C)	THICKNESS						*_	Refer to Standard Drawings 715-PHCL-18	
	CTD DIATE ALLIMINIUM ALLOW DIATE (C)	CORR. PROFILE						1	and -19 for nominal diameter appropriate	
	STR. PLATE ALUMINUM ALLOY PLATE (C)	THICKNESS		9" x 2 1/2"				1	for pay item diameter.	
	CTD DIATE ALL DIVINITION OF CO.	CORR. PROFILE		0.1	1			1		
	STR. PLATE ALUMINUM ALLOY PLATE W/ CFP (C)	THICKNESS						**_	Tabulated thickness refers to top and	
		CORR. PROFILE		6" x 2"				1	side plates. Bottom plates shall be of	
	STR. PLATE STEEL PIPE (C)	THICKNESS **		0.111	1			1	next greater available thickness.	
		CORR. PROFILE			1			1	_	
	STR. PLATE STEEL PIPE W/ CFP (C)	THICKNESS **			+			1		
			1	1	1	1		1		
								1		

ARTER TO STERE TO STERE	
ARTER HAMILIAN ARTER	
STATE OF STATE OF AND	
WILLIAM OVAL ENGINEERING	

RECOMMENDED FOR APPROVAL	B. K Stall	DESIGN ENGINEER	04/28/2017 DATE	- 11
DESIGNED:	CCW	DRAWN:	DJG	-
CHECKED:	ВКА	CHECKED:	BSS	-

HAMILTON COUNTY HIGHWAY DEPARTMENT

STRUCTURE DATA TABLE

AND PIPE MATERIAL TABLE

HORIZONTAL SCALE

3/8"=1'-0"

HAMILTON CO. BR. 306

VERTICAL SCALE

DESIGNATION

N/A

PB-14-0004

SURVEY BOOK

SHEETS


30 of 39


CONTRACT


PROJECT

PB-14-0004

lay 25, 2017, 9:58am User Name: bstutzman








Date: May 25, 2017, 2:19pm User Name: bstutzman File: M: \[ \textstyle 2014 \| 2014 \| 214-0030 \| Road \| CAD \| CrossSect \| Line A Xsec

HIGHWAY DEPARTMENT 04/28/2017 DATE DESIGN ENGINEER 1"=10' PB-14-0004 SURVEY BOOK SHEETS MDV DESIGNED: 33 of 39 **CROSS SECTIONS** PROJECT CONTRACT BKA CHECKED: CHECKED: PB-14-0004



DESIGNED:

CHECKED:

BKA

MDV

BSS

CHECKED:

CROSS SECTIONS

SURVEY BOOK

CONTRACT


SHEETS

34 of 39

PROJECT

PB-14-0004

Date: May 25, 2017, 10:01am User Name: bstutzman File: M·1 2014/214-0030|Road|CAD|CrossSect|Line A



DESIGNED:

CHECKED:

BKA

MDV

BSS

CHECKED:

**CROSS SECTIONS** 


35 of 39


PROJECT


PB-14-0004

CONTRACT


Date: May 25, 2017, 10:01am User Name: bstutzman File: M·1 20141214-00301Road1CAD1CrossSectVine 4 Xs









				HAMILTON COUNTY	HORIZONTAL SCALE BRIDGE FIL		E		
RECOMMENDED					1"=10'	HAMILTON CO. BR. 306			
FOR APPROVAL	04/28/2017		04/28/2017	HIGHWAY DEPARTMENT	VERTICAL SCALE	DESIGNATION			
		DESIGN ENGINEER DATE			1"=10'		PB-14-000	4	
DESIGNED:	MDV DRAWN:	DD ALA/NI	DD AMAL MDV		SURVEY BOOK		SHEETS		
		MDV	CROSS SECTIONS		38	of	39		
CHECKED:	ВКА	CHECKED: BSS	DCC	CROSS SECTIONS	CONTRACT		PROJECT		
							PB-14-000	4	





# MUD CREEK WETLAND MITIGATION

# HAMILTON COUNTY, INDIANA












# ISSUED FOR BID

# INTERIM DESIGN NOTE:

Portions of the work shown on this plan set are identified to be completed by others at a later date.

# CERTIFIED:





BRIAN J. MEUNIER, P.E.
INDIANA REGISTRATION No. PE11300321
EXPIRATION DATE: JULY 2018

MUD CREEK WETLAND MITIGATION

HAMILTON COUNTY, INDIANA

4/26/2017 Project 19.R160411.00001

#### **GENERAL NOTES**

- 1. The CONTRACTOR shall not perform work on any day between the hours of 7:00 p.m. to 7:00 a.m. or on Sunday and Holidays without prior approval from OWNER.
- 2. The CONTRACTOR and any SUB-CONTRACTORS shall comply with the state and local laws and federal requirements of the Occupational Safety and Health Act of 1970 (OSHA), as they relate to their operations.
- 3. The CONTRACTOR shall be required to comply with all state, local, and federal regulations regarding air, water and noise pollution. The CONTRACTOR shall not build fires on the site.
- 4. The CONTRACTOR shall ensure that all employees and applicants employed in the performance of work with respect to hire, tenure, terms, conditions or privileges of employment of any matter directly related to employment will not be discriminated against because of race, religion, color, sex, disability, national
- 5. The CONTRACTOR shall be solely responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with the work and shall take all necessary precautions for the safety of all employees, visitors, equipment, or other property at the site or adjacent thereto, including trees, shrubs, lawns, walks, pavements, roadways, structures, utilities, and underground facilities not designated for removal, relocation, or replacement on the plans.
- 6. The CONTRACTOR shall call the Indiana Underground Plant Protection Service ("Holey-Moley") by dialing 811 at least 48 hours prior to commencement of landdisturbing activities to schedule a utility locate. It is the CONTRACTOR'S responsibility to verify the location of all existing utilities and to report any discrepancies or omissions with the existing utilities shown on the plans to the ENGINEER immediately.
- 7. The CONTRACTOR shall protect all existing utilities as required to prevent damage. All utilities must be fully operational and accessible throughout the duration of the project. Any and all damage to existing utilities must be repaired in kind at the CONTRACTOR'S expense.
- 8. There shall be no storage of equipment, materials, debris, soil, etc. in the street or right-of-way without written permission from the City of Fishers.
- 9. There shall be no storage of equipment, materials, debris, soil, etc. within the floodway of Mud Creek.
- 10. Temporary traffic control is the responsibility of the CONTRACTOR. The CONTRACTOR shall coordinate with the City of Fishers to determine exact traffic control requirements.
- 11. The CONTRACTOR shall minimize interference with adjoining roads, streets, walks, and other adjacent occupied or used facilities during construction operations. The CONTRACTOR shall not close or obstruct streets walks, or other adjacent occupied or used facilities without permission from the OWNER and authorities having jurisdiction. The CONTRACTOR may cross roads and streets during the performance of the work if necessary, at the approval of the OWNER, however, the CONTRACTOR shall protect all roads and streets at heavy-equipment crossings as needed to protect pavement. The CONTRACTOR shall provide road barriers and/or a flag person to control traffic during all times when construction equipment is crossing public roads or when otherwise warranted.
- 12. Any pavement or curb damaged by construction activity shall be replaced in kind by the CONTRACTOR at no cost to the OWNER.
- 13. If the CONTRACTOR finds a conflict, error or discrepancy in the construction documents of plans, the CONTRACTOR shall so report to the ENGINEER by email at once before proceeding with the work affected thereby and shall obtain a written interpretation or clarification from the ENGINEER.
- 14. All work shall be constructed in accordance with the lines and grades shown on the plans. The full responsibility for keeping alignment and grades shall rest upon the CONTRACTOR at no additional cost to the OWNER.
- 15. The CONTRACTOR shall immediately remove mud tracked by his vehicles onto the public roadways when the road is in use, otherwise, before a closed section is returned to service.
- 16. The excavation shall be maintained such that positive drainage is provided at all times. The CONTRACTOR shall be responsible for all costs associated with dewatering of any excavation in order to provide positive drainage and any costs associated with the disposal of such water.
- 17. The temporary erosion control system installed by the CONTRACTOR shall be properly maintained as indicated on the plans of as directed by the OWNER to control erosion and siltation at all times during the life of the contract. This work shall include repair of the various systems, removal of trapped sediment and cleaning or replacement of any silt filter fabric or other control measures. Accumulated silt in the work areas shall be removed from the site as an incidental cost to the project, or shall be used on-site if approved by the OWNER. Any additional materials and work required by the ENGINEER to control erosion shall be measured and paid for as specified. If the CONTRACTOR fails to maintain the temporary erosion control system as directed by the ENGINEER, the OWNER may at the expiration of a period of 48 hours, after having given the CONTRACTOR written notice, proceed to maintain the systems as deemed necessary, and the cost thereof be deducted from and compensation due the CONTRACTOR under this contract.
- 18. The CONTRACTOR shall obtain permission from the necessary stakeholders for all work performed outside of the OWNER'S right-of-way.
- 19. The CONTRACTOR shall be fully responsible to the OWNER for all acts and omissions of his SUB-CONTRACTORS, suppliers, and other persons and organizations performing of furnishing any of the work or goods under a direct or indirect contract with the CONTRACTOR just as the CONTRACTOR is

- responsible for the CONTRACTOR'S own acts and omissions. The CONTRACTOR shall assume sole obligation for the payment of any monies due the any SUB-CONTRACTOR, supplier, or other person or organization, except as may be otherwise required by laws and regulations.
- 20. Upon completion of the work and prior to acceptance of the project, the CONTRACTOR shall be required to furnish the OWNER and ENGINEER each with one set of marked-up plans showing the as-constructed location and elevations of all construction components.
- 21. The CONTRACTOR shall be responsible to secure the construction site against unauthorized entrance by persons and vehicles outside of and during working hours. This includes securing the site against dumping and trespassers. The cost of any additional security measures deemed necessary by the CONTRACTOR shall be incidental to the contract. If the CONTRACTOR fails to maintain security of safety measures at the project site, the OWNER may at the expiration of a period of 48 hours, after having given the CONTRACTOR written notice, proceed to provide additional measures as deemed necessary, and the cost thereof shall be deducted from any compensation due, or which may become due to the CONTRACTOR under this contract.
- 22. The CONTRACTOR shall allow the OWNER, ENGINEER, or OWNER'S representative's access to the site at all times.
- 23. The OWNER is responsible for the following permits for this project:
  - a. Indiana Department of Natural Resources Construction in a Floodway
  - b. Indiana Department of Environmental Management Section 401 Water Quality Certification,
  - c. United States Army Corps of Engineers Section 404 Permit, and
  - d. Indiana Department of Environmental Management Rule 5 Permit.
- Copies of all permits obtained will be provided to the CONTRACTOR by the OWNER. The CONTRACTOR is responsible for compliance with permit conditions and requirements. The CONTRACTOR shall be responsible for obtaining all other permits and/or licenses as required by law/ordinance or regulation.
- 24. Do not work in the waterway from April 1 through April 30 without prior written approval from the Indiana Department of Natural Resources Division of Fish and
- 25. Do not cut any trees suitable for Indiana bat roosting (greater than 3-inches DBH, living or dead, with loose hanging bark) from April 1 to September 30.

#### **CONSTRUCTION NOTES**

- 1. The CONTRACTOR shall stake out and mark limits of construction so they are clearly visible. All construction activities shall be performed within the designated construction limits.
- 2. The CONTRACTOR shall clearly mark all underground utilities, culverts, and underground drains prior to construction.
- 3. The CONTRACTOR shall deploy suitable equipment for the excavation, compaction, and grading of soil to construct the work. The CONTRACTOR shall perform excavation to the lines and grades shown on the plans.
- 4. Responsibility for the repair of utilities and structures when broken or otherwise damaged shall be borne by the CONTRACTOR. Materials damaged by the CONTRACTOR during handling or placement operations shall be replaced inkind by the CONTRACTOR at CONTRACTOR'S sole expense. Such damaged materials shall be removed from the site by the CONTRACTOR.
- 5. The CONTRACTOR shall provide sufficient dewatering equipment and make satisfactory arrangements for the disposal of water collected or removed during construction without undue interference with other work or damage to surrounding property. The CONTRACTOR shall not place fill or topsoil within construction areas containing standing water. If the CONTRACTOR uses pumping equipment, care and measures shall be deployed to minimize intake of sediments and scouring at discharge points.
- 6. All demolition items shall be removed from the site at the CONTRACTOR'S
- 7. Throughout the project duration, the contractor shall ensure positive drainage is maintained on the exposed soils to prevent excess absorption of rainfall. Ruts, holes, and other depressed areas shall be filled immediately to prevent ponding.
- 8. The use of explosives is NOT permitted.
- 9. Open burning is NOT permitted. 10. Items noted or otherwise identified to be salvaged (if any) shall be returned to
- the OWNER in the original condition. 11. The CONTRACTOR shall remove all reusable topsoil from excavation areas for
- placement on final graded areas.
- 12. The CONTRACTOR shall not stockpile any material on-site overnight or during non-working hours. Spoil material resulting from the work shall be stockpiled at an offsite location. The location and extent of the stockpile shall be the responsibility of the CONTRACTOR. CONTRACTOR shall comply with all federal, state, and local requirements when stockpiling spoil materials. CONTRACTOR shall provide OWNER with a site layout and copies of all required permit approvals for any offsite stockpile or laydown areas.
- 13. Topsoil shall be placed in one loose lift in all areas where the underlying soils will not support vegetative growth. If adequate topsoil volumes are not available from on-site sources, the CONTRACTOR shall amend available soil to produce a suitable growth medium. The final surface shall be graded smooth to final design grades. All significant surface variations, including vehicle tire or equipment track ruts, shall be smoothed out with a grader box or other method. Final grading performed by dozers shall be done in a manner such that the track cleats are oriented parallel to the contours to minimize runoff velocity down the slope and to help maintain moisture in the topsoil to promote vegetative growth.
- 14. Shop drawings of product certification information of all constructed of supplied project materials shall be submitted to the OWNER of ENGINEER for review prior to implementation or installation.
- 15. Upon substantial completion and again at final completion of construction, prior to demobilization, the CONTRACTOR shall ensure that all excess construction materials and debris, including unsuitable soils, tree limbs, brush, trash, temporary erosion control measures, and miscellaneous construction materials are removed from the project site and disposed of properly. All disturbed areas shall be restored to the satisfaction of the OWNER and ENGINEER.
- 16. The CONTRACTOR shall repair erosion damage to the finished surfaces at no additional cost to the OWNER. Accumulated sediment form erosion shall be removed by CONTRACTOR at no additional cost to the OWNER.
- 17. The CONTRACTOR shall maintain final grades and vegetation in the wetland areas until the vegetation is established and accepted by the OWNER. The CONTRACTOR shall repair erosion damage to the finished surfaces and vegetation at his own expense.
- 18. The CONTRACTOR shall perform post-construction maintenance on the new vegetation for a period of two (2) year from substantial completion. Vegetation must be established and accepted by the OWNER prior to final completion and release of retainage.

### Work to be completed by Contractor under current contract:

- 1. Installation and maintenance of temporary erosion control measures
- Installation of construction entrance
- 3. Topsoil clearing, mass grading, fine grading, topsoil placement, and micro-grading inside area identified as 'Deed Restricted Area'

DSGN.

DWN.

CHKD.

- 4. Installation of live plant material, trees, shrubs, and seeding
- 5. Installation of environmental signage ("Do not mow Do not spray" signs)
- 6. Installation of permanent erosion control measures
- 7. Removal of temporary erosion control measures

#### Work to be completed by Others under separate contract: 1. Installation of pedestrian trail subbase, HMA, and footbridges

2. Earthwork outside of 'Deed Restricted Area'

#### **GENERAL CONSTRUCTION SEQUENCE**

- 1. This General Construction Sequence has been assembled for project guidance and may be adjusted to meet the CONTRACTOR'S specific plans; however, the sequence of Step 2 through Step 6 shall not be altered. The CONTRACTOR shall generally perform the following steps to complete the project.
- 2. Stake the construction limits.
- 3. Locate, mark, and protect all existing utilities.
- 4. Install temporary traffic control measures as required by the City of Fishers.
- 5. Construct staging area and construction entrance.
- Install silt fence as indicated on the plans. 7. Remove topsoil for areas to be disturbed within construction limits.
- 8. Excavate and grade constructed wetland area as indicated on the plans.
- 9. Construct clay cap in planned open water areas of wetland pods as indicated on the plans.
- 10. Apply topsoil to all areas that are to be seeded.
- 11. Install wetland plantings as indicated on the plans.
- 12. Pedestrian trail footbridges indicated on the plans to be completed by others at a
- 13. Install environmental signage along pedestrian trail as indicated on plans.
- 14. Stabilize all disturbed areas of the project that are completed, as work proceeds, with temporary or permanent seeding, mulch, and erosion control blankets as described on the drawings. Apply fertilizer, lime (if needed), mulch, and seed to permanently stabilize.
- 15. Remove temporary erosion control measures upon OWNER'S approval and after vegetation is established and approved by the ENGINEER.
- 16. The CONTRACTOR shall provide to the OWNER and ENGINEER an updated as-built topographic survey which includes documentation of all aspects of the project.

Briz. 4/26/17

**GENERAL NOTES** 

GN1

19.R160411.0000

SHEET 2 OF 10

PROJECT NO.

DRAWING NO.

CHRISTOPHER B. BURKE ENGINEERING, LLC PNC Center. Suite 1368 South 115 West Washington Street Indianapolis, Indiana 46204 (317) 266-8000 FAX: (317) 632-3306

MUD CREEK WETLAND MITIGATION

PROJECT:

HAMILTON COUNTY, INDIANA


1 4/26/17 ISSUED FOR BID NO. DATE FILE NAME R:\2016\16-0411.00000\CAD\DGN Files\20170405\160411\_GN1.dgn

BJM SCALE NATURE OF REVISION CHKD.

DATE: 5/22/2017

J. MEUNING SISTER NO. No. PE11300321 BWM AS NOTED NOIANE NONAL ENG

DJW



FILE NAME R:\2016\16-0411.00000\CAD\DGN Files\20170405\160411\_EX1.dgn

HAMILTON COUNTY, INDIANA

SURVEY ORIGINALLY COMPLETED FOR TOWN OF FISHERS AND USED WITH PERMISSION.

Project: 106th Street and Cumberland Road - Intersection Improvement

Client: Town of Fishers, Indiana

This project is located in Sections 5, 6, 7 & 8, Township 17 North, Range 5 East of the Second Principal Meridian, Town of Fishers, Delaware & Fall Creek Townships, Hamilton County, Indiana. The scope of this project was to obtain data to be used for possible design improvements to the intersection of 106th Street and Cumberland Road. A Location Control Route Survey Plat (LCRSP) with accompanying original survey field book and topographic data was to be provided to the client. The LCRSP will serve as a basis of describing any right-of-way required for said improvements. It is not a property retracement survey. Any apparent property lines and corners, subdivision lines and corners, or section lines and corners are based upon physical evidence or testimony. If additional U.S.P.L.S.S. corners are required for said improvements, they should be tied

The Basis of Bearing for the survey is the Indiana State Plane Coordinate System (ISPCS), East Zone (NAD 83 2011), which is a grid coordinate system. The horizontal control system was established by using the National Geodetic Survey's Online Positioning User Service (OPUS). Using Trimble R6 GPS equipment, an OPUS solution was performed at Control Point #1, and the following information resulted from said

Latitude: N 39°56'27.17875" Longitude: W 85°59'45.89717" Northing: 1709333.2349 Easting: 235716.6382

Trimble Business Center (TBC) software using a least squares adjustment was used in the processing of the GPS data. The following information pertains to said control

Projection Name: Indiana State Plane Coordinate System - East Zone Projection Type: Transverse Mercator Horizontal Datum: North American Datum of 1983 (NAD 83), 2011 Adjustment Geoid Model: GEOID12A Reference Frame: WGS 84

After the horizontal control system was established, it was converted to a local, ground system by scaling the control data from said grid system to a ground system using a combination factor of X=1.0000555630 (1/X=0.999944440) that was applied at Control Point #1. The system was then translated by subtracting 1,699,333.2349 from all northings and by subtracting 225,716.6382 from all eastings of each point. This resulted in Control Point #1 having local, ground coordinates of N: 10,000.0000, E: 10,000.0000. No rotation was performed. All distances and coordinates shown hereon are ground distances and coordinates.

The vertical datum of the project was established by holding Indiana Department of Natural Resources Benchmark HAM 86, 1989 which has a published elevation of 784.773 feet. It is on the National Geodetic Vertical Datum of 1929 (NGVD 29). Additional temporary benchmarks were established through differential leveling using a Sokkia automatic level. The project's vertical datum is NGVD 1929.

Cross-sections and topographic information within the project limits were collected using Trimble R6 GPS equipment, a Nikon total station, and an electronic field book. The topography of the project is graphically represented in AutoCAD Civil 3D 2012 format and coordinate information is provided in a ".txt" file in the following format: Point Number, Northing, Easting, Elevation, Description

Right-of-way and deed line information is shown per subdivision plats and deeds on file with the Office of the Recorder of Hamilton County, Indiana. Where no right-ofway records exist, the existing right-of-way is shown as the edge of the travel lane. Owner information shown is based on current tax records in the Auditor's Office of

In accordance with Title 865 of the Indiana Administrative Code, the following observations and opinions are offered regarding the monuments found or set for the survey. Unless otherwise noted, all monuments found and set were found or set

Harrison Monuments were found at the north quarter corner of Section 7 (Pnt. #18), the northeast corner of Section 7 (Pnt. #19), the north quarter corner of Section 8 (Pnt. #20), the east quarter corner of Section 6 (Pnt. #21) and the east quarter corner of Section 7 (Pnt. #22) all in Township 17 North, Range 5 East per Hamilton County Surveyor reference ties. The uncertainty associated with the locations of these monuments, in my opinion, is negligible.

The uncertainty associated with the locations of any of the route survey control lines due to occupation or possession lines, in my opinion, is negligible.

This survey (performed in the field from March 4, 2013 to March 25, 2013 under my supervision), to the best of my knowledge and belief, was executed according to the provisions of Title 865 of the Indiana Administrative Code regarding route surveys, covering the entire survey.

The project's original coordinate system was the Indiana State Plane Coordinate System East Zone. It was established by performing an Opus solution at CP #1 which resulted in the following values: N:1709333.2349, E:235716.6382, Lat: 39°56'27.17875"N, Long:85°59'45.89717"W. The project was moved to a local, ground system by scaling all data by the Opus solution combination factor of 1.0000555630 (1/X=0.999944440) holding CP #1 as the base point. The data was then translated by subtracting 1,699,333.2349 from all northings and by subtracting 225,716.6382 from all eastings. This resulted in CP#1 having the coordinates of N:10000.0000, E:10000.0000. All distances and coordinates are local, ground distances and coordinates.

NOTE: FOLLOWING THE ORIGINAL SURVEY, THE SURVEY AND DESIGN DATA WAS SHIFTED TO ALLOW CP#1 TO REGAIN THE ORIGINAL, STATE PLANE COORDINATE VALUES: N:1709333.2349, E:235716.6382, Lat: 39°56'27.17875"N, Long:85°59'45.89717"W. MINOR DIFFERENCES BETWEEN TRUE STATE PLANE COORDINATES AND THE CURRENT PROJECT'S COORDINATE SYSTEM MAY OCCUR.




**EXISTING CONDITIONS** 

PROJECT NO. 19.R160411.00000 SHEET 3 OF 10

DRAWING NO.

EX1



#### Seed Mix A - Emergent Herbaceous Seed Mix

Common Name	Scientific Name	Ounces/Acre
Grasses and Sedges:		
Bristly Sedge	Carex comosa	4
Porcupine Sedge	Carex hystericina	2
Lurid Sedge	Carex Iurida	4
Fox Sedge	Carex vulpinoidea	5
Blunt Spike Rush	Eleocharis obtusa	2
Rice Cut Grass	Leersia oryzoides	2
Soft Rush	Juncus effusus	0.5
Hard-Stemmed Bulrush	Scirpus acutus	2
Dark Green Bulrush	Scirpus atrovirens	0.5
Softstem Bulrush	Scirpus validus	2
Forbs:	+	
Sweet Flag	Acorus americanus	2
Water Plantain	Alisma subcordatum	2
Marsh Milkweed	Asclepias incarnata	3
False Aster	Boltonia latisquama	2
Spotted Joe-Pye Weed	Eupatorium maculatum	2
Autumn Sneezeweed	Helenium autumnale	2
Swamp Rose Mallow	Hibiscus palustris	2
Blue Flag	Iris virginica shrevei	2
Cardinal Flower	Lobelia cardinalis	0.5
Great Blue Lobelia	Lobelia siphilitica	0.5
Water Horehound	Lycopus americanus	2
Monkeyflower	Mimulus ringens	1
Arrow Arum	Peltandra virginica	10
Ditch Stonecrop	Penthorum sedoides	1
Pickerel Weed	Pontedaria cordata	6
Common Arrowhead	Sagittaria latifolia	2
Giant Burreed	Sparganium eurycarpum	4
Blue Vervain	Verbena hastata	2

#### Seed Mix B - Native Grass Seed Mix

Common Name	Scientific Name	Ounces/Acre	
Graminoids:			
Big Bluestem	Andropogon gerardii	16	
Canada Wild Rye	Elymus canadensis	32	
Virginia Wild Rye	Elymus virginicus	12	
Switchgrass	Panicum virgatum	4	
Little Bluestem	Schizachyrium scoparium	32	
Indian Grass	Sorghastrum nutans	16	
Forbs:			
Smooth Aster	Aster laevis	1	
New England Aster	Aster novae-angliae	2	
White False Indigo	Baptisia leucantha	2	
Wild Senna	Cassia hebecarpa	2	
Tall Coreopsis	Coreopsis tripteris	2	
Purple Coneflower	Echinacea purpurera	4	
Rattlesnake Master	Eryngium yuccifolium	3	
Sawtooth Sunflower	Helianthus grosseserratus	1	
Western Sunflower	Helianthus occidentalis	1	
False Sunflower	Heliopsis helianthoides	3	
Prairie Blazing Star	Liatris pycnostachya	1	
Bergamot	Monarda fistulosa	0.5	
Foxglove Beardtongue	Penstemon digitalis	0.5	
Purple Prairie Clover	Petalostemum virginianum	1	
Prairie Cinquefoil	Potentilla arguta	1	
Mountain Mint	Pycnanthemum virginianum	0.5	
Yellow Coneflower	Ratibida pinnata	4	
Black-Eyed Susan	Rudbeckia hirta	4	
Sweet Black-Eyed Susan	Rudbeckia submentosa	3	
Rosinweed	Silphium integrifolium	2	
Compass Plant	Silphium laciniatum	2	
Prairie Dock	Silphium terebinthinaceum	2	
Stiff Goldenrod	Solidago rigida	2	
Riddell's Goldenrod	Solidago riddellii	1	
Tall Ironweed	Vernonia altissima	2	
Culver's Root	Veronicastrum virginicum	0.5	
Temporary Cover:		Pounds/Acre	
Seed Oats	Avena sativa	25	
Annual Rye Grass	Lolium perenne	25	

#### Seed Mix C - Wetland Forest Seed Mix

Common Name	Scientific Name	Ounces/Acre
Grasses and Sedges:		
Tall Brome	Bromus latiglumis	2
Frank's Sedge	Carex frankii	2
Spreading Oval Sedge	Carex normalis	1
Fox Sedge	Carex vulpinoidea	2
Wood Reed	Cinna arundinacea	2
Fowl Manna Grass	Glyceria striata	1
Bottlebrush Grass	Hystrix patula	4
Riverbank Wild Rye	Elymus riparius	8
Virginia Wild Rye	Elymus virginicus	4
Forbs & Wildflowers:		
Wingstem	Actinomeris alternifolia	2
Calico Aster	Aster lateriflorus	2
Panicled Aster	Aster simplex	1
Hairy Wood Mint	Blephilia hirsuta	1
False Sunflower	Heliopsis helianthoides	2
Great Blue Lobelia	Lobelia siphilitica	0.5
Branched Coneflower	Rudbeckia triloba	2
Tall Coneflower	Rudbeckia laciniata	2
Cupplant	Silphium perfoliatum	2
Late Goldenrod	Solidago gigantea	1
Temporary Cover:		Pounds/Acre
Seed Oats	Avena sativa	
		32
Annual Rye Grass	Lolium perenne	10
Timothy	Phleum pretense	2


Α	Blue Flag	Iris virginica shrevei
В	White Water Lily	Nymphaea alba
С	Pickerel Weed	Pontedaria cordata
D	Giant Burreed	Sparganium eurycarpum

#### PLANTING SPECIFICATIONS


- All trees must be obtained from within 200 miles of the project site.
- Planting should occur in the fall between the months of September and November, or in the spring before leaves are present.
- · The above ground portions of each plant shall be healthy and vigorous, and free of disease, discoloration, infestation or deformity.
- Containers or burlap shall be free of any plant species not specified below; specifically weedy, noxious, invasive, and/or non-native species.
- The hole for the plant should be dug to a width that is twice the diameter of the root ball,
- If roots have spiraled around the pot, use a knife to slice down the sides of the root ball in 3 to 4 places. If tree is balled and burlap, cut the burlap away from the trunk of the tree before installation.
- Before planting the tree or shrub, prune it to remove any damaged branches.
- When planted, the tree or shrub should be at or slightly above ground level.
- Straighten the plant and backfill with topsoil. Be sure to eliminate air pockets, and water
- · Proper tree staking should be utilized where necessary.

PROJECT:


		Wetland		Quantity for	Quantity for
Common Name	Scientific name	Indicator	Tree/Shrub	Wetland Pod 'A'	Wetland Pod 'B'
Hackberry	Celtis occidentalis	FAC	Tree	9	11
Spicebush	Lindera benzoin	FACW	Shrub	4	5
American Sycamore	Platanus occidentalis	FACW	Tree	9	11
Swamp White Oak	Quercus bicolor	FACW	Tree	9	11
Bur Oak	Quercus macrocarpa	FAC	Tree	9	11
American Elm	Ulmus americana	FACW	Tree	9	11
Gray Dogwood	Cornus racemosa	FACW	Shrub	4	5
Buttonbush	Cephalanthus occidentalis	OBL	Shrub	4	5
River Birch	Betula nigra	FACW	Tree	9	11
Shumard Oak	Quercus shumardii	FACW	Tree	9	11
Black Chokeberry	Aronia melanocarpa	FACW	Shrub	4	5
				79	97



TREES SHALL BE PLANTED AT 12-FT ON CENTER SHRUBS SHALL BE PLANTED BETWEEN EVERY OTHER TREE (6-FT FROM THE NEAREST 12-FT O.C. TREE SPACING).



TREE AND SHRUB DETAILS



**CONSTRUCTION NOTE** 

CONSTRUCTION ITEMS NOT HALF-TONED REPRESENT WORK TO BE COMPLETED AS PART OF THIS PHASE. REMAINING WORK (HALF-TONED) TO BE COMPLETED BY OTHERS AT A LÂTER DATE.

# SIGN MOUNTING TYPE 'A' NOT TO SCALE

(317) 266-8000

CHRISTOPHER B. BURKE ENGINEERING, LLC PNC Center, Suite 1368 South 115 West Washington Street Indianapolis, Indiana 46204 FAX: (317) 632-3306

SEED MIXES

NOT TO SCALE

MUD CREEK WETLAND MITIGATION

HAMILTON COUNTY, INDIANA


NO. DATE

Briz. 4/26/17 DSGN. DJW DWN. BWM CHKD. 1 4/26/17 ISSUED FOR BID BJM SCALE AS NOTED CHKD. NATURE OF REVISION FILE NAME R:\2016\16-0411.00000\CAD\DGN Files\20170405\160411\_MD2.dgn DATE:

No. NOIANA


WETLAND AND SIGNAGE DETAILS PROJECT NO. 19.R160411.00000 SHEET 5 OF 10 DRAWING NO.

MD2




CITY OF FISHERS STANDARD DRAWING


MULTI-USE TRAIL TYPICAL DETAIL



NOTE: LIVE PLANT MATERIAL TO BE INSTALLED AFTER INSTALLATION OF CLAY CAP. SUITABLE TOPSOIL SHALL ENCAPSULATE THE ROOT SYSTEM AND SHALL PENETRATE THE FULL THICKNESS OF THE CLAY CAP.



CLAY CAP DETAIL (2) NOT TO SCALE



#### **LOADING & DESIGN CRITERIA:**

- 1. ANY MODIFICATIONS TO THIS PLAN MUST BE APPROVED
- BY ENGINEER GROUND SNOW LOAD: Pg = 70 PSF (REDUCED IN COMBINATION WITH PEDESTRIAN LOAD)
   DECK LIVE LOAD: PEDESTRIAN (AASHTO) = 85 PSF
- STRINGER LIVE LOAD DEFLECTION LIMIT: L / 360
  BRIDGE STRUCTURE SHALL MEET ADA REQUIREMENTS.
  MAXIMUM SPACING BETWEEN PLANKS MUST NOT EXCEED 1/2" AFTER SEASONING.

#### LUMBER:

- 1. LUMBER FOR STINGERS, DECKING, CURB, POSTS, SILL, AND BLOCKING SHALL BE NO. 2 (OR BETTER) PRESSURE TREATED SOUTHERN YELLOW PINE 2. DRAWINGS ARE PREPARED USING S4S FINISHED DIMENSIONS UNLESS NOTED OTHERWISE. IF ROUGH
- SAWN LUMBER IS USED, ADJUST DIMENSIONS AS 3. ALL LUMBER SHALL BE SAWN AND FABRICATED PRIOR
  TO PRESSURE TREATMENT WITH RESPECTIVE
  PRESERVATIVE

#### HARDWARE:

- 1. ALL BOLTS, WASHERS, NUTS, AND MISCELLANOUS METAL HARDWARE SHALL BE ASTM 307 HOT DIPPED
- GALVANIZED 2. FASTENERS SHALL BE HOT DIPPED GALVANIZED RING SHANK NAILS OR WOOD SCREWS. DRIFT PINS SHALL BE DEFORMED NO. 6 REINFORCING BARS MEETING ASTM A615.

#### GLUE:


1. APPLY GLUE BETWEEN EACH LAMINATION USING A WATERPROOF EXTERIOR ADHESIVE COMPATIBLE WITH THE PRESERVATIVE TREATMENT SUCH AS PL-500 BY CONTECH, OR APPROVED EQUAL. APPLY %" CONTINUOUS BEAD @ 1%" O.C.


#### **CONSTRUCTION:**

- 1. SILLS SHALL BEAR ON NATIVE SOIL OR LEDGE ROCK FREE FROM COMPRESSIBLE ORGANIC MATERIAL AND CAPABLE OF SUPPORTING THE
- BRIDGE UNDER FULL LOAD. PROVIDE UNIFORM BEARING UNDER ENTIRE LENGTH OF SILL.
- 2. STRINGERS WITH CAMBER SHALL BE POSITIONED SO THAT THE CAMBER IS UP AND KNOTS NEAR THE EDGE WILL BE IN THE TOP HALF OF THE STRINGERS

  3. DECKING PLANKS SHALL BE LAID WITH THE HEART
- SIDE DOWN.

  4. LAG BOLTS AND LAG SCREWS SHALL BE TIGHENED UNTIL THE WOOD MATERIAL BEGINS TO COMPRESS.





/ 2X4 CURB - %" GALV. ROUND HEAD LAG 4X4 CURB POST

**CURB DETAIL** 

ADAPTED FROM THE U.S. FOREST SERVICE STANDARD PEDESTRIAN BRIDGE DETAILS.

TYPICAL FOOTBRIDGE FRAMING DETAILS

# **CONSTRUCTION NOTE**

CONSTRUCTION ITEMS NOT HALF-TONED REPRESENT WORK TO BE COMPLETED AS PART OF THIS PHASE. REMAINING WORK (HALF-TONED) TO BE COMPLETED BY OTHERS AT A LATER DATE.

CHRISTOPHER B. BURKE ENGINEERING, LLC PNC Center, Suite 1368 South

115 West Washington Street Indianapolis, Indiana 46204 (317) 266-8000 FAX: (317) 632-3306 MUD CREEK WETLAND MITIGATION

HAMILTON COUNTY, INDIANA

PROJECT:


DSGN. DJW DWN. 1 4/26/17 ISSUED FOR BID SCALE AS NOTED CHKD. NO. DATE NATURE OF REVISION FILE NAME R:\2016\16-0411.00000\CAD\DGN Files\20170405\160411\_MD3.dgn




MISCELLANEOUS DETAILS

PROJECT NO. 19.R160411.00000 SHEET 6 OF 10 DRAWING NO.

MD3





## SOILS MAP

# SOIL DESCRIPTION

#### Sh – Shoals silt Ioam

This soil map unit occurs in flood plains. Shoals and similar soils make up 90 percent of soil composition. This somewhat poorly drained soil has a moderate permeability, low shrink-swell potential, and high potential for frost action. The surface runoff is slow. Organic matter content is moderate. The available water capacity is high. The potential for corrosion is high for steel and low for concrete.

Based on soil properties, the Shoals soils are rated somewhat to very limited which signifies that the soil has properties that are moderately favorable for the specified use and the limitations can be overcome or minimized by special planning, design, or installation. Fair performance and moderate maintenance can be expected. The soil also has properties that are unfavorable for the specified use and the limitations generally cannot be overcome without major soil reclamation, special design, or expensive installation procedures. Poor performance and high maintenance can be expected. The Shoals soils are very limited for shallow excavations due to depth of saturated zone, flooding and unstable excavation walls. Shoal soils are very limited for use as pond reservoir area due to seepage. Shoal soils are somewhat limited for paths and trails due to depth to saturated zone, flooding and dust.

#### We – Westland silty clay loam

This soil map unit occurs in depressions on outwash plains. This poorly drained soil has slow permeability, moderate shrink-swell potential, and high for frost action. The surface runoff is ponded or is very slow. Organic matter content is high. The available water capacity is high. The potential for corrosion is high for steel and low for concrete.

Based on soil properties, the Westland soils are very limited which signifies that the soil has properties that are unfavorable for the specified use and the limitations generally cannot be overcome without major soil reclamation, special design, or expensive installation procedures. Poor performance and high maintenance can be expected. Westland soils are very limited for shallow excavations due to depth to saturated zone, ponding, and unstable excavation walls. Westland soils are very limited for use as pond reservoir area due to seepage. Westland soils are very limited for paths and trails due to depth to saturated zone, ponding, and dust.

### PROJECT DESCRIPTION

The purpose of the project will be to construct forested and emergent wetlands to mitigate for wetland disturbance related to the Cyntheanne Road Bridge replacement. Minor grading adjustments are planned to promote an environment suitable for the planned wetland types. A multiuse trail that passes around the perimeter and between the wetland pods will be completed by others at a later date.

# PERSON ON-SITE RESPONSIBLE FOR EROSION AND SEDIMENT CONTROL


FARAZ KHAN 1700 S. 10TH STREET NOBLESVILLE, IN 46060


317-773-7770 FARAZ.KHAN@HAMILTONCOUNTY.IN.GOV

CHRISTOPHER B. BURKE ENGINEERING, LLC
PNC Center, Suite 1368 South
115 West Washington Street
Indianapolis, Indiana 46204
(317) 266-8000 FAX: (317) 632-3306

MUD CREEK WETLAND MITIGATION

HAMILTON COUNTY, INDIANA





STORMWATER POLLUTION PREVENTION PLAN EXISTING CONDITIONS


PROJECT NO.

19.R160411.00000

SHEET 7 OF 10

DRAWING NO.

SW1



CHRISTOPHER B. BURKE ENGINEERING, LLC PNC Center, Suite 1368 South

PROPOSED SITE

PROJECT:

PNC Center, Suite 1368 South
115 West Washington Street
Indianapolis, Indiana 46204
(317) 266-8000 FAX: (317) 632-3306

MUD CREEK WETLAND MITIGATION

HAMILTON COUNTY, INDIANA

| DSGN. | DSGN. | DWN. | DWN.

BJM

DJW

BWM

| PE11300321 | STATE OF | AS NOTED | A/26/2017

STORMWATER POLLUTIOIN
PREVENTION PLAN
PROPOSED CONDITIONS

PROJECT NO.

19.R160411.00000


SHEET 8 OF 10

DRAWING NO.


SW2

#### **CONSTRUCTION NOTE**

CONSTRUCTION ITEMS NOT HALF-TONED REPRESENT WORK TO BE COMPLETED AS PART OF THIS PHASE. REMAINING WORK (HALF-TONED) TO BE COMPLETED BY OTHERS AT A LATER DATE.



#### SECTION



### STABILIZED CONSTRUCTION ENTRANCE

### Requirements:

1. Construction entrance material shall be 6 inches of washed stone (INDOT No. 53) on geotextile fabric.

<u>PLAN</u>

- 2. Construction entrance width shall be 20-feet minimum or full width of
- entrance/exit, whichever is greater. 3. Construction entrance shall have a minimum length of 50-feet.

- Avoid locating on steep slopes or at curves in public roads.
   Remove all vegetation and questionable material from the foundation area, and grade and crown for positive drainage.
- 3. If slope towards road exceeds 2%, construct a 6-8-inches high water bar (ridge) with 3:1 side slopes across the foundation area about 15-feet from the entrance to divert runoff away from the road.
- 4. Install pipe under pad if needed to maintain proper public road drainage.
- 5. Geotextile underliner fabric shall be installed on the graded foundation. 6. Place stone to dimensions and grade shown on plans, leaving surface smooth
- and sloped for drainage.
- 7. Divert all surface runoff and drainage from the stone pad to a sediment trap or


#### Maintenance:

Inspect construction access road weekly and after each storm event or heavy use. Reshape as needed for drainage and runoff control. Topdress with clean stone as needed. Immediately remove mud and sediment tracked or washed into public roads by brushing or sweeping. Flushing should only be used if the water is conveyed into a sediment trap or basin. Repair any broken road pavement immediately.


#### Post-Construction:

Remove construction access road stone and geotextile after construction activities have been completed and approved by the Onsite Representative or Owner. Restore all disturbed area to pre-construction conditions to the satisfaction of ownership. This may require topsoil placement and grading, and seeding; Equipment should remain onsite to accomplish this to the satisfaction of ownership.

PROJECT:



SIDE VIEW



### SILT FENCE


#### Requirements:

- 1. Fence posts shall be buried 18-inches minimum below the ground surface. 2. Fence posts shall be spaced at a maximum of 6-feet laterally.
- 3. Silt fence fabric shall be buried 8-inches minimum below the ground
- 4. Fence post shall have a minimum height above the ground surface of 24inches.

- 1. Dig an 8-inch deep trench along proposed fence line (a trenching machine
- is needed on long runs). 2. Pound stake in trench 18-inches minimum. Be sure to stretch fabric taut when pounding stakes. (Note: Stake must be on the downhill or downstream side of the fence).
- 3. Drape loose end of geotextile into trench.
- 4. Backfill and compact soil on both sides.

# Maintenance:

Inspect the silt fence periodically and after each storm event. If fence fabric tears, starts to decompose, or in any way becomes ineffective, replace the affected portion immediately. Remove deposited sediment when it reaches half the height of the fence at its lowest point or is causing the fabric to bulge. Take care to avoid undermining the fence during cleanout. After the contributing drainage area has been stabilized, remove the fence and sediment deposits, bring the disturbed area to grade and stabilize.



# ISOMETRIC VIEW

### PAVED AREA INLET PROTECTION

#### Requirements:

- The inlet protection unit shall be a sewn geotextile fabric unit.
- 2. The unit shall have lifting straps to allow removal of the unit and manual inspection of the storm water system.

- Remove the grate from the inlet and stand on end.
- 2. Move the top lifting straps out of the way and place the grate into the Dandy Sack in a manner so that the grate is below the top straps and above the lower straps.
- Insert the grate into the inlet using the lifting straps.


#### Maintenance:

Inspect the unit after each storm event and on a weekly basis. All accumulated sediment and debris around the unit are to be removed after each storm event. Empty the unit if the containment area is more than 1/3 full of sediment. To empty, utilize the lifting straps to lift the unit out of the inlet. Remove the grate. Transport the unit to an appropriate location for removal of the contents. Reinstall unit as described above.

STABILIZED CONSTRUCTION ENTRANCE DETAIL NOT TO SCALE

SILT FENCE DETAIL

PAVED AREA INLET PROTECTION DETAIL




FAX: (317) 632-3306

MUD CREEK WETLAND MITIGATION

NO. DATE

DSGN. DJW DWN. BWM CHKD. 1 4/26/17 ISSUED FOR BID BJM SCALE AS NOTED CHKD. NATURE OF REVISION FILE NAME R:\2016\16-0411.00000\CAD\DGN Files\20170405\160411\_SW3.dgn DATE: 4/26/2017




STORMWATER POLLUTION PREVENTION PLAN

PROJECT NO. 19.R160411.00000 SHEET 9 OF 10 DRAWING NO.

SW3

HAMILTON COUNTY, INDIANA

NOTES AND DETAILS



**SLOPE INSTALLATION** 

- 1. PREPARE SOIL BEFORE INSTALLING ROLLED EROSION CONTROL PRODUCTS (RECP's), INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED. a. NOTE: WHEN USING CELL-O-SEED DO NOT SEED PREPARED AREA. CELL-O-SEED
- MUST BE INSTALLED WITH PAPER SIDE DOWN. 2. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE RECP'S IN A 6" (15 CM) DEEP X 6" (15 CM) WIDE TRENCH WITH APPROXIMATELY 12" (30cm) OF RECP's EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE RECP's WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30 CM) APART IN THE BOTTOM OF THE TRENCH.BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" (30 CM) PORTION OF RECP'S BACK OVER SEED AND COMPACTED SOIL. SECURE RECP'S OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" (30 CM) APART ACROSS THE WIDTH OF THE RECP's.
- 3. ROLL THE RECP's (A.) DOWN OR (B.) HORIZONTALLY ACROSS THE SLOPE. RECP's WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL RECP's MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING THE DOT SYSTEM, STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN.
- 4. THE EDGES OF PARALLEL RECP's MUST BE STAPLED WITH APPROXIMATELY 2" 5" (5 CM - 12.5 CM) OVERLAP DEPENDINGON RECP's TYPE.
- 5. CONSECUTIVE RECP'S SPLICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE (7.5 CM) OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" (30 CM) APART ACROSS ENTIRE RECP's
- a. NOTE: \*IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" (15 CM) MAY BE NECESSARY TO PROPERLY SECURE THE

#### **EROSION CONTROL BLANKET**

### Requirements:

North American Green S150BN erosion control blanket or approved


### Installation:

- 1. Begin at the top of the slope by anchoring the blanket in a 6-inch by 6-inch wide trench with approximately 12-inches of blanket extended beyond the up-slope portion of the trench. Anchor the blanket with a row of staples/stakes approximately 12-inches apart in the bottom of the trench. Backfill and compact the trench after stapling.
- 2. Roll the blanket down the slope, blankets will unroll with the appropriate side against the soil surface. All blankets must be securely fastened to soil surface by placing staples/stakes in appropriate locations as per manufacturer's specifications.
- 3. The edges of parallel blankets must be stapled with approximately 2- to 5inches overlap. Place the edges of the overlapping blanket even with the colored seam stitch on the previously installed blanket.
- 4. Consecutive blankets spliced down the slope must be placed end over end (shingle style) with an appropriate 3-inches overlap. Staple through overlapped area, approximately 12-inches apart across entire blanket
- 5. Install seeding as specified by manufacturer.
- 6. Install erosion control blanket at locations specified on plans.

#### <u>Maintenance:</u>

During vegetative establishment, inspect after storm events for erosion below the blanket. If any area shows erosion, pull back the portion of the blanket covering it, add soil, reseed the area, and re-lay and staple the blanket. After vegetative establishment, check the treated area periodically. Add additional staples as necessary to securely anchor the erosion control blanket.





(FOR USE IN AREAS WITH WHERE 3H:1V ≤ SLOPE < 2H:1V)

DETAIL SOURCE: NORTH AMERICAN GREEN



#### **TEMPORARY VEGETATION**

Plant species shall be selected on the basis of quick germination, growth, and time of year. Seeding should be done as often as possible following construction activity. Daily seeding on rough graded areas when the soil is loose and moist is usually most effective.

Temporary Seed Bed Preparation:

- Test soil to determine its nutrient levels. 2. Fertilize as recommended by soil testing. If testing is not done, apply 400-
- 600 lbs/acre of 12-12-12 analysis, or equivalent, fertilizer. 3. Work the fertilizer into the soil 2-4-inches deep with a disc or rake operated across the slope.

#### Temporary Seeding:

Use temporary seed mixed as specified on plans.

- 2. Apply seed uniformly with a drill or cultipacker-seeder or by broadcasting, and cover to the appropriate depth for the seed used.
- 3. If drilling or broadcasting, firm the seedbed with a roller or cultipacker.
- 4. Mulch seeded area to increase seeding success. Anchor all mulch by tackifying.

#### <u>Maintenance:</u>

Inspect periodically after planting to ensure that vegetative stands are adequately established; reseed if necessary. Check for erosion damage after storm event and repair; reseed and mulch if necessary.

#### PERMANENT VEGETATION

Plant species shall be selected on the basis of soil type, soil pH, region of the state, time of year, and planned use of the area to be seeded. Follow requirements in Mitigation Plan document for the stream mitigation site.

Permanent Seed Bed Preparation:

- Test soil to determine pH and nutrient levels.
- 2. If soil pH is unsuitable for the species to be seeded, apply lime according to test recommendations.
- 3. Till the soil to obtain a uniform seedbed, working the fertilizer and lime into the soil 2-4-inches deep with a disc or rake operated across the

#### Permanent Seeding:


Optimum seeding dates are March 1 through May 10 and August 10 through September 30. Permanent seeding done between May 10 and August 10 may need to be irrigated. As an alternative, use temporary seeding until the preferred date for permanent seeding.

- 1. Use seed mix as specified on Sheet MD2.
- 2. Apply seed uniformly with a drill, cultipacker-seeder, or by broadcast,
- and cover to a depth of 1/4 to 1/2-inches. 3. If drilling or broadcasting, firm the seedbed with a roller or cultipacker.
- 4. Mulch all seeded areas and anchor with a tackifver. Use erosion control blankets on areas sloping 4:1 or steeper if erosion becomes a problem or if directed by the ENGINEER. (Note: if seeding is done with a hydroseeder, fertilize and mulch can be applied with the seed in a slurry mixture).

#### Maintenance

Inspect periodically, especially after storm events, until the stand is successfully established (characteristics of a successful stand include: vigorous dark green or blue-ish green seedings; uniform density with nurse plants, legumes, and grasses well intermixed; and the perennials remaining green throughout the summer, at least at the plant base). Add fertilizer the following growing season according to soil test recommendations. Repair damaged, bare or sparse areas by filling any gullies, refertilizing, over- or reseeding. If plant cover is sparse or patchy, review the plant material chosen, soil fertility, moisture condition, and mulching after re-preparing the seedbed. If vegetation fails to grow, perform soil testing to determine acidity or nutrient deficiency problems. If additional fertilization is needed to get a satisfactory stand, do so according to soil test recommendations.

# SEEDING NOTES



#### EROSION CONTROL SEQUENCE


- Before construction, stake the project limits. 2. Install perimeter protection in the form of silt fence around construction
- limits noted on the plans. 3. Strip topsoil from site as necessary for completion of project, except for
- the high flow shelf area. 4. Install new construction access road(s). Throughout construction, CONTRACTOR shall control dust on the project site with water trucks. CONTRACTOR shall perform street sweeping as necessary to keep public and private roadways being used as transportation routes clean of
- dirt, dust, and incidental construction debris. 5. paved area inlet protection as noted on the plans to be completed by others at a later date.
- 6. Perform all necessary site grading. CONTRACTOR shall minimize size, area of disturbance, and time of exposure.
- 7. Place seed, fertilizer, and mulch on all remaining disturbed areas, as shown in the drawings.
- 8. Maintain erosion and sediment practices throughout the duration of the
- 9. Remove all temporary erosion control measures upon OWNER'S approval and after vegetation is established and approved by the ENGINEER.

#### ENERAL NOTES FOR EROSION AND SEDIMENT CONTROL SEQUENCE 1. The CONTRACTOR shall install, monitor, and maintain all required

- erosion control measures in accordance with Indiana 327 Rule 5, and the "Indiana Storm Water Quality Manual", which is hereby incorporated in these drawings by reference and made a part thereof.
- 2. Temporary erosion and sediment control features to prevent sediment from leaving the site shown on the plans are at approximate locations. Erosion control features shall be inspected following each rainfall event. Accumulated sediment shall be removed immediately. Damaged erosion and sediment control features shall be repaired and replaced
- 3. Construction debris and waste, such as garbage, debris, cleaning waste, etc., shall be removed from the site and kept out of water courses. Proper disposal and management of all waste is required. 4. The duration of time which an area remains exposed shall be kept to a
- practical minimum depending on the weather. If construction activity is to cease for more than 14 days, the disturbed areas shall be temporarily
- 5. Temporary erosion control features include construction entrance, silt fencing, rock check dam, and vegetation.
- 6. Permanent vegetation will serve as the only permanent erosion control
- 7. Permanently stabilize with seed and mulch all disturbed areas that are completed. Place temporary seed and mulch in all disturbed areas that are unable to be permanently seeded. 8. Throughout construction, maintain the erosion control measures as
- described on the plans. Remove all silt from the project site after permanent vegetation is
- established; redistribute in appropriate areas or dispose offsite.

EROSION CONTROL NOTES






MUD CREEK WETLAND MITIGATION

HAMILTON COUNTY, INDIANA

PROJECT:

1 4/26/17 ISSUED FOR BID NO. DATE NATURE OF REVISION FILE NAME R:\2016\16-0411.00000\CAD\DGN Files\20170405\160411\_SW4.dgn

DSGN. DJW DWN. BWM CHKD. BJM SCALE AS NOTED CHKD. 4/26/2017 DATE:



STORMWATER POLLUTION PREVENTION PLAN NOTES AND DETAILS

PROJECT NO. 19.R160411.00000 SHEET 10 OF 10

DRAWING NO. SW4